

<b>Original signed by</b>	<b>Robyn Pearson</b>	<b>on</b>	<b>5/07/2022</b>
	<b>Date determined:</b>		<b>5/07/2022</b>
	<b>Date operates:</b>		<b>5/07/2022</b>
	<b>Date lapses:</b>		<b>5/07/2027</b>

Claire and Ian Morgan  
5 Ryries Parade  
CREMORNE NSW 2090

D311/21  
RT (CIS)

**ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED**  
**NOTICE OF DETERMINATION - Approval**

---

**Development Application Number:** 311/21

---

**Land to which this applies:** 5 Ryries Parade, Cremorne  
Lot No.: 52, DP: 10291

---

**Applicant:** Claire Brooksley Morgan and Ian Richard Morgan

---

**Proposal:** Alterations and additions to dwelling house including ground floor alterations and additions, a first-floor addition, a carport and associated works.

---

**Determination of Development Application:** Subject to the provisions of Section 4.17 of *the Environmental Planning and Assessment Act 1979*, approval has been granted subject to conditions in the notice of determination.

---

**Date of Determination:** 5 July 2022

---

**Reasons for Approval** The development application has been assessed against the North Sydney Environmental Plan 2013 and the North Sydney Development Control Plan 2013 and generally found to be satisfactory.

The proposed development complies with the LEP maximum building height control and key DCP controls including site coverage and the minimum setback requirements.

A view assessment based on the Tenacity view sharing principles has also been carried out to ascertain the impacts on views for an adjoining property located at the rear of the subject site.

---

---

It is concluded that the proposal is unlikely to cause adverse material impacts to adjoining properties.

The issues raised in the submissions have been addressed in the assessment report.

Having regard to the provisions of Section 4.15 (1) of the Environmental Planning & Assessment Act 1979, the proposed development will not result in any unreasonable amenity or environmental impacts. The application is considered satisfactory and is recommended for approval subject to the imposition of appropriate conditions.

---

**Consent to operate from:** 5 July 2022

---

**Consent will lapse on:** 5 July 2027

---

**Period of Consent**

Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite 5 July 2027.

---

**How community views were taken into account:**

The application has been notified in accordance with Council's Community Engagement Protocol with adjoining properties and the Willoughby Bay Precinct notified between 22 October and 05 November 2021.

The amended plans were notified to the owners of the adjoining properties, previous submitters and the precinct for 14 days between 4 and 18 March 2022. Council received a total of eight (8) submissions including two (2) submissions in support of the proposal. The issues raised in the submissions have been addressed in the assessment report.

---

**Review of determination and right of appeal:**

Within six months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

---

Plans endorsed by the consent authority - please refer to condition A1.

**Endorsed for and on behalf of North Sydney Council**

**5 July 2022**

\_\_\_\_\_  
DATE

\_\_\_\_\_  
Signature on behalf of consent authority  
ROBYN PEARSON  
**TEAM LEADER (ASSESSMENTS)**

---

(i) **Conditions**

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the *Environmental Planning and Assessment Act 1979* ("the Act") and the provisions of the *Environmental Planning and Assessment Regulation 2000* ("the Regulation") such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

(ii) **Definitions**

Unless specified otherwise, words have the same meaning as defined by the Act, the Regulation and the *Interpretation Act 1987* as in force at the date of consent.

**Applicant** means the applicant for this consent.

**Approved Plans** means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

**AS** or **AS/NZS** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

**NCC** means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

**Council** means North Sydney Council.

**Court** means the Land and Environment Court.

**Local Native Plants** means species of native plant endemic to North Sydney LGA.

**Stormwater Drainage System** means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

**Owner** means the owner of the *site* and successors in title to the *site*.

**Owner Builder** has the same meaning as in the *Home Building Act 1989*.

**Principal Certifier** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

**Principal Contractor** for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

**Professional Engineer** has the same meaning as in the *NCC*.

**Public Place** has the same meaning as in the *Local Government Act 1993*.

**Road** has the same meaning as in the *Roads Act 1993*.

**SEE** means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

**Site** means the land being developed subject to this consent.

**NSLEP 2013** means *North Sydney Local Environmental Plan 2013*

**NSDCP 2013** means *North Sydney Development Control Plan 2013*

**Work** for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: **Interpretation of Conditions** - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

**INDEX OF CONDITIONS**

	<b>Page No.</b>
<b>A. Conditions that Identify Approved Plans</b>	
A1. Development in Accordance with Plans/Documentation	8
A2. Plans on Site	8
A3. No Demolition of Extra Fabric	8
<b>C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)</b>	
C1. Screen Planting	8
C2. Revised Landscape Plan	9
C3. Dilapidation Report Damage to Public Infrastructure	9
C4. Structural Adequacy of Existing Building	10
C5. Sediment Control	10
C6. Waste Management Plan	10
C7. External Colours and Finishes	11
C8. External Finishes and Materials	11
C9. Roofing Materials - Reflectivity	11
C10. Obtain Driveway Crossing Permit under S.138 Roads Act 1993	11
C11. Stormwater Management and Disposal Design Plan - Construction Issue Detail	12
C12. Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	13
C13. Tree Bond for Public Trees	14
C14. Protection of Trees	14
C15. Approval for Removal of Trees	15
C16. Garbage and Recycling Facilities	15
C17. Asbestos and Hazardous Material Survey	15
C18. Air Conditioners in Residential Premises	16
C19. Section 7.12 Contributions	16
C20. Security Deposit/Guarantee Schedule	17
C21. BASIX Certificate	17
<b>D. Prior to the Commencement of any Works (and continuing where indicated)</b>	
D1. Protection of Trees	17
D2. Temporary Fences and Tree Protection	18
D3. Public Liability Insurance - Works on Public Land	18
D4. Commencement of Works' Notice	18
<b>E. During Demolition and Building Work</b>	
E1. Parking Restrictions	18
E2. Road Reserve Safety	19
E3. Temporary Disposal of Stormwater Runoff	19
E4. Service Adjustments	19
E5. Council Inspection of Public Infrastructure Works	19
E6. Removal of Extra Fabric	20
E7. Dust Emission and Air Quality	20

E8.	Noise and Vibration	20
E9.	No Work on Public Open Space	20
E10.	Developer's Cost of Work on Council Property	20
E11.	No Removal of Trees on Public Property	21
E12.	Protection of Trees	21
E13.	Special Permits	21
E14.	Construction Hours	22
E15.	Installation and Maintenance of Sediment Control	23
E16.	Sediment and Erosion Control Signage	23
E17.	Site Amenities and Facilities	23
E18.	Health and Safety	23
E19.	Prohibition on Use of Pavements	24
E20.	Plant and Equipment Kept Within Site	24
E21.	Imported Fill Material	24
E22.	Waste Disposal	24
E23.	Asbestos Removal	24

***F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation***

F1.	National Construction Code	25
F2.	Home Building Act	25
F3.	Appointment of a Principal Certifying Authority (PCA)	25
F4.	Construction Certificate	26
F5.	Occupation Certificate	26
F6.	Excavation/Demolition	26
F7.	Protection of Public Places	26
F8.	Site Sign	27

***G. Prior to the Issue of an Occupation Certificate***

G1.	Infrastructure Repair and Completion of Works	27
G2.	Certification - Civil Works	27
G3.	Damage to Adjoining Properties	28
G4.	Utility Services	28
G5.	Asbestos Clearance Certificate	28
G6.	Disposal Information	28
G7.	Height	29
G8.	BASIX Completion Certificate	29
G9.	Unpaved Verge	29
G10.	Compliance with Certain Conditions	29

***I. Ongoing/Operational Conditions***

I1.	Single Occupancy	29
I2.	Maintenance of Approved Landscaping	29

**A. Conditions that Identify Approved Plans**

**Development in Accordance with Plans/Documentation**

- A1. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

<b>Plan No.</b>	<b>Description</b>	<b>Dated</b>
Unnumbered	Site plan/site analysis	21-02-2022
Unnumbered	Lower ground floor	21-02-2022
Unnumbered	Ground floor plan	21-02-2022
Unnumbered	First floor plan	21-02-2022
Unnumbered	Section AA and BB	21-02-2022
Unnumbered	South and west elevation	21-02-2022
Unnumbered	North and east elevation	21-02-2022

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

**Plans on Site**

- A2. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

**No Demolition of Extra Fabric**

- A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

**C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)**

**Screen Planting**

- C1. To maintain acceptable levels of privacy, screen planting must be installed and maintained along the rear (eastern) property boundary of the site in location shown clouded in red on the stamped approved plans.

The required screen planting must consist of suitable screening species capable of attaining a mature height of 3.0 m above finished ground levels.



Details of the screen planting required by this condition must be provided to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the details submitted fully satisfy the requirements of this condition.

(Reason: To preserve privacy of the adjoining properties.)

### **Revised Landscape Plan**

C2. The applicant must submit a landscape plan, based on the landscape plan dated 21 February 2021, incorporating the following:

- (a) 1 x *Lagerstroemia indica* (45 l) shall be planted within the front setback;
- (b) 2 x *Lagerstroemia indica* (45 l) shall be planted within the rear setback area;
- (c) Screen planting with a mature height of 3m shall be planted along the rear (western) property boundary as required by Condition C1 in this consent; and
- (d) Existing driveway, crossover and tyre strips shall be retained, and no new concrete slab shall be installed.

The landscape plan must be submitted for the written approval of Council's Team Leader Assessment in consultation with Council's Landscape Officer.

The Certifying Authority must ensure that the Council's written approval, landscape plan and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure a desirable landscaping outcome for the subject site and the locality.)

### **Dilapidation Report Damage to Public Infrastructure**

C3. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

**Structural Adequacy of Existing Building**

- C4. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the property and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Certifying Authority for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

(Reason: To ensure the structural integrity of the building is maintained)

**Sediment Control**

- C5. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils and Construction* (4th edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

**Waste Management Plan**

- C6. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:

- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
- b) The design of the on-site waste storage and recycling area; and
- c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

#### **External Colours and Finishes**

C7. The external colours and finishes shall match those as existing and/or be compatible with surrounding development. A schedule of external colours and finishes must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that the completed colours and finishes of the works are compatible with surrounding development)

#### **Roofing Materials - Reflectivity**

C8. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

#### **Obtain Driveway Crossing Permit under S.138 Roads Act 1993**

C9. Prior to the issue of the Construction Certificate, North Sydney Council must issue the applicant with a driveway crossing and road infrastructure works **permit** to suit the approved off-street parking facilities. To obtain the permit, an application must be made to Council on a '*Vehicular Access Application*' form with payment of the adopted assessment/inspection fees. Council will require civil design construction drawings and certification from the applicant's Civil Engineer to verify design details and enable permit issue. The responsibility for accuracy of the design fully rests with the designing engineer. All responsibility on implementation and supervision of works specified on design plans fully rests on designing engineer or whoever is chosen to be applicant's engineering representative. The civil design drawings shall detail **the following infrastructure construction requirements of Council in relation to the consent:**

- a) The proposed vehicular access ways must comply with AS 2890.1 and Council's current Vehicular Access Application Guidelines and Specification (gutter bridges not permitted) to ensure that a B85 vehicle will not scrape/strike the surface of the carriageway, layback, vehicular crossing or parking floor.
- b) The width of the vehicular layback must be 4.5 m (including the wings).
- c) The vehicular laybacks must be set square to the kerb.
- d) The crossing (between the layback and the property boundary) must be perpendicular on a single straight grade of approximately 4.5%, falling to the back of the layback.
- e) The boundary footpath levels must match the existing levels and shall not be altered unless agreed to by Council.

- f) The kerb gutter, and 1200 mm road shoulder wide- strip, adjacent to all new layback and gutter works, on Ryries Parade must be reconstructed, to ensure uniformity in the road reserve.
- g) All inspection openings, utility services must be adjusted to match the proposed driveway levels and location.
- h) The design detail has to be provided with **vehicular access application** and must include sections along centre-line and extremities of the crossing at a scale of 1:25. Sections are to be taken from the centre of the roadway through to the parking area itself and shall include all changes of grade and levels, **both** existing and proposed.
- i) A longitudinal section along the gutter line of Ryries Parade at a scale of 1:50 showing how it is intended to transition the layback with the existing gutter levels and shall include all changes of grade and levels, **both** existing and proposed.
- j) A longitudinal section along the footpath property boundary at a scale of 1:50 is required and shall include all changes of grade and levels, **both** existing and proposed.
- k) The sections must show the calculated clearance to the underside of any overhead structure.
- l) Pipelines within the footpath area must be hot dipped galvanized rectangular steel hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.
- m) Any footpath panel on Ryries Parade that is disturbed for the purpose of stormwater connection must be reconstructed as a whole panel.

The permit must be granted by Council prior to the issue of any Construction Certificate.

All driveway and infrastructure works on the road reserve must be undertaken in accordance with the terms of the permit issued by Council. Inspections by Council will be required as specified. The Certifying Authority issuing the Construction Certificate must ensure that the permit issued by Council is obtained and referenced on and accompanies the Construction Certificate issued.

(Reason: To facilitate appropriate vehicular access to private sites, without disruption to pedestrian and vehicular traffic)

#### **Stormwater Management and Disposal Design Plan - Construction Issue Detail**

- C10. Prior to issue of any Construction Certificate, a site drainage management plan must be prepared by a qualified drainage design engineer. The site drainage management plan must detail the following requirements of North Sydney Council:
- a) Compliance with BCA drainage requirements, Councils Engineering Performance guide and current Australian Standards and guidelines, such as AS/NZ3500.3.2 1998, National Plumbing and Drainage Code.
  - b) Stormwater runoff and subsoil drainage generated by the approved dwellings must be conveyed in a controlled manner by gravity to Council's kerb in Ryries Parade.
  - c) All redundant stormwater pipelines within the footpath area shall be removed and the footpath and kerb reinstated.
  - d) Pipelines within the footpath area shall be hot dipped galvanized steel rectangular hollow section with a minimum wall thickness of 4.0 millimetres and a section height of 100 millimetres.
  - e) Any footpath panel on Ryries Parade disturbed for the purpose of stormwater connection shall be reconstructed as whole panel.

Details demonstrating compliance are to be submitted with the Construction Certificate.

The Certifying Authority issuing the Construction Certificate must ensure that the approved drainage plan and specifications, satisfying the requirements of this condition, is referenced on and accompanies the Construction Certificate.

(Reason: To ensure controlled stormwater management and disposal without nuisance)

**Bond for Damage and Completion of Infrastructure Works - Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement**

C11. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of **\$4,500.00** to be held by Council for the payment of cost for any/all of the following:

- a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
- b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and environmental controls) required in connection with this consent.
- c) remedying any defects in any such public work that arise within six months after the work is completed.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

**Tree Bond for Public Trees**

C12. Prior to the issue of any construction certificate, security in the sum of **\$11,000.00** must be provided to Council for the protection of trees in public places, including the making good of any damage caused to such trees. The security is to be provided in accordance with the Schedule below.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate but only upon inspection and release by Council's Landscape Development Officer.

If any tree is removed or damaged Council may deduct from this security the reasonable cost of replacement with a tree of the same species and to a similar stage of growth it would have attained at the completion of the work.

In the case of any tree, which cannot be replaced with a similar specimen, the security for that tree will be forfeited to Council and used to provide replacement street plantings.

SCHEDULE

Tree	Location	Bond
<i>Camellia sasanqua</i> (6 m x 6 m)	Council verge in front of 5 Ryries Parade	\$4,000.00
<i>Callistemon viminalis</i> (12 m x 12 m)	Council verge in front of 5 Ryries Parade	\$7,000.00

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

**Protection of Trees**

C13. The above street trees shall be protected in accordance with AS4970, 18 m high tree protection fencing to be installed around entire verge for duration of works, no pruning shall be permitted.

Street Trees	Location
<i>Camellia sasanqua</i> (6 m x 6 m)	Council verge in front of 5 Ryries Parade
<i>Callistemon viminalis</i> (12 m x 12 m)	Council verge in front of 5 Ryries Parade

All other site and neighbouring trees shall be retained and protected including:

Other Trees	Location
1 x <i>Plumeria sp</i> (7 m x 10 m)	Within the front setback of subject site
1 x <i>Camellia sp.</i> (4 m x 4 m)	Within the front setback of subject site
1 x <i>Lagerstroemia indica</i> (12 m x 8 m)	Within the adjoining property No.7 Ryries Parade

Sensitive construction techniques including hand excavation, pier and beam construction, flexible locations of piers/footings shall be used within the TPZ of these trees, no roots greater than 30 mm shall be cut, tree protection fencing shall be installed.

Minor pruning to these trees, of minor branches only, up to no more than 10% of canopy may be carried out by AQ3 arborist in accordance with AS4373.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

**Approval for Removal of Trees**

C14. The following tree(s) are approved for removal in accordance with the development consent:

<b>Tree</b>	<b>Location</b>
1 x small tree (3 m x 2 m)	Adjacent to the side (western) boundary identified for removal in the submitted landscape plan dated 21 February 2022

Removal or pruning of any other tree on the site is not approved, excluding species exempt under Council’s Tree Preservation Order.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

**Garbage and Recycling Facilities**

C15. Adequate provision must be made for the storage of waste and recyclable material generated by the premises. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the provision of appropriate waste facilities and to ensure efficient collection of waste by collection contractors)

**Asbestos and Hazardous Material Survey**

C16. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating “DANGER ASBESTOS REMOVAL IN PROGRESS” must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans,

referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not put at risk unnecessarily)

#### **Air Conditioners in Residential Premises**

C17. The use of any air conditioner installed on the premises must comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2008 and State Environmental Planning Policy (Infrastructure) 2007 and must not:

- (a) emit a noise that is audible within a habitable room in any affected residence (regardless of whether any door or window to that room is open);
  - (i) before 8.00 am and after 10.00 pm on any Saturday, Sunday or Public Holiday; or
  - (ii) before 7.00 am or after 10.00 pm on any other day
- (b) cause an LAeq(15min) which exceeds the RBL background noise level by more than 5dB when measured at the boundary of any affected residence. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy will be applied.

“affected residence” includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation and hospitals.

“boundary” includes any window or elevated window of an affected residence.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain residential amenity)

#### **Section 7.12 Contributions**

C18. A monetary contribution pursuant to the provisions of Section 7.12 of *the Environmental Planning and Assessment Act 1979* is to be paid to Council, in accordance with the North Sydney Council’s Contribution Plan, to provide for local infrastructure improvements.

Based on the cost of development at the date of determination, the total contribution payable to Council is **\$6,165.50**.

#### **Indexation**

The monetary contribution required under this consent will be indexed at the time of payment in accordance with quarterly movements in the Consumer Price Index (All Groups Index) for Sydney as published by the Australian Bureau of Statistics.

#### **Timing of Payment**

The contribution MUST be paid to Council prior to issue of any Construction Certificate for any work approved by this consent.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council’s Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council’s website at [www.northsydney.nsw.gov.au](http://www.northsydney.nsw.gov.au).



(Reason: To provide for local infrastructure identified in the North Sydney Council Local Contributions Plan 2020)

**Security Deposit/Guarantee Schedule**

C19. All fees and security deposits/guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

<b>Security Deposit/Guarantee</b>	<b>Amount (\$)</b>
Street Tree Bond (on Council Property)	\$11,000.00
Engineering Construction Bond	4,500.00
<b>TOTAL BONDS</b>	<b>\$15,500.00</b>

Note: The following fees applicable

<b>Fees</b>	
Section 7.12 Contribution	\$6,165.00
<b>TOTAL FEES</b>	<b>\$6,165.00</b>

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

**BASIX Certificate**

C20. Under clause 97A(3) of the Environmental Planning and Assessment Regulation 2000, it is a condition of this development consent that all the commitments listed in BASIX Certificate No. **A433475\_02** for the development are fulfilled. Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the proposed development will meet the Government's requirements for sustainability and statutory requirements)

***D. Prior to the Commencement of any Works (and continuing where indicated)***

**Protection of Trees**

D1. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

**Temporary Fences and Tree Protection**

- D2. All protected trees on-site that are specifically nominated as per condition C46 to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builders' waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites), not less than the distance shown in the schedule hereunder, must be installed to the satisfaction of the Certifying Authority prior to demolition or commencement of any works and must be maintained for the duration of the works:

(Reason: To protect the trees to be retained on the site during construction works)

**Public Liability Insurance - Works on Public Land**

- D3. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

**Commencement of Works' Notice**

- D4. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

***E. During Demolition and Building Work***

**Parking Restrictions**

- E1. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during works)

### **Road Reserve Safety**

- E2. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". **If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.**

(Reason: Public Safety)

### **Temporary Disposal of Stormwater Runoff**

- E3. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

### **Service Adjustments**

- E4. Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the person acting on the consent and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the Applicants full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services at the appropriate stage of the development (including water, phone, gas and the like). Council accepts no responsibility whatsoever for any matter arising from its approval of this application involving any influence upon utility services provided by another authority.

(Reason: To ensure the service requirements are met)

### **Council Inspection of Public Infrastructure Works**

- E5. During the works on public infrastructure reverting to Council's care and control, Council's development engineer may undertake inspections of the works at the following hold points:

- a) Vehicular access; and associated road civil works.

All works must proceed in accordance with Roads Act 1993 approvals or other permits relating to roads issued by Council. A minimum of 48 hours' notice must be given to Council to book an inspection. Work must not proceed until the works or activity covered by the inspection is approved.

(Reason: To ensure quality of construction joints and connections in the drainage system)

**Removal of Extra Fabric**

E6. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

**Dust Emission and Air Quality**

E7. The following must be complied with at all times:

- (a) Materials must not be burnt on the site.
- (b) Vehicles entering and leaving the site with soil or fill material must be covered.
- (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines - Managing Urban Stormwater: Soils and Construction.
- (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

**Noise and Vibration**

E8. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

**No Work on Public Open Space**

E9. No work can be undertaken within adjoining public lands (i.e., Parks, Reserves, Roads etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.

(Reason: Protection of existing public infrastructure and land and to ensure public safety and proper management of public land)

**Developer's Cost of Work on Council Property**

E10. The developer must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

**No Removal of Trees on Public Property**

- E11. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.

(Reason: Protection of existing environmental infrastructure and community assets)

**Protection of Trees**

- E12. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

**Notes:**

- a. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- b. An application to modify this consent pursuant to Section 4.55 of the Environmental Planning and Assessment Act 1979 will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

**Special Permits**

- E13. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours' notice is required for any permit:

**1) On-street mobile plant**

E.g., cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

**2) Hoardings**

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

**3) Storage of building materials and building waste containers (skips) on Council's property**

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

**4) Kerbside restrictions, construction zones**

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

**Construction Hours**

E14. Construction activities and works approved under this consent must be carried out only within the hours stipulated in the following table:

Location	Standard Construction Hours	
	Day	Hours
All Other Zones	Monday - Friday	7.00 am - 5.00 pm
	Saturday	8.00 am - 1.00 pm
	Sunday, Public holiday	No work permitted

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance and Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

**Installation and Maintenance of Sediment Control**

E15. Erosion and sediment controls must be installed and maintained at all times in accordance with the

Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

### **Sediment and Erosion Control Signage**

E16. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

### **Site Amenities and Facilities**

E17. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of workplace determines the type of amenities required.

Further information and details can be obtained from the Internet at [www.workcover.nsw.gov.au](http://www.workcover.nsw.gov.au).

(Reason: To ensure the health and safety of the community and workers on the site)

### **Health and Safety**

E18. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at [www.workcover.nsw.gov.au](http://www.workcover.nsw.gov.au).

(Reason: To ensure the health and safety of the community and workers on the site)

### **Prohibition on Use of Pavements**

E19. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

**Plant and Equipment Kept Within Site**

- E20. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at [www.northsydney.nsw.gov.au](http://www.northsydney.nsw.gov.au).

(Reason: To ensure public safety and amenity on public land)

**Imported Fill Material**

- E21. The only waste derived fill material that may be received at the development site is:
- a) Virgin excavated natural material (within the meaning of the Protection of the Environment Operations Act 1997); and
  - b) Any other waste-derived material the subject of a resource recovery exemption under cl. 51A of the Protection of the Environment Operations (Waste) Regulation 2005 that is permitted to be used as fill material.

Any waste-derived material the subject of a resource recovery exemption received at the development site, must be accompanied by documentation as the material's compliance with the exemption conditions and must be provided to the Certifying Authority on request.

(Reason: To ensure that imported fill is of an acceptable standard for environmental protection purposes)

**Waste Disposal**

- E22. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

**Asbestos Removal**

- E23. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)



**F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation**

**National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

**Home Building Act**

F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:

a) in the case of work for which a principal contractor is required to be appointed:

- i) the name and licence number of the principal contractor, and
- ii) the name of the insurer by which the work is insured under Part 6 of that Act, or

(b) in the case of work to be done by an owner-builder:

- (i) the name of the owner-builder, and
- (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

2) If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

**Appointment of a Principal Certifying Authority (PCA)**

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

**Construction Certificate**

F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

**Occupation Certificate**

F5. A person must not commence occupation or use of the whole or any part of a new building (*new building* includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

**Excavation/Demolition**

- F6.
- 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
  - 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
  - 3) Demolition work must be undertaken in accordance with the provisions of AS2601- Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

**Protection of Public Places**

- F7.
- 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
  - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
  - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
  - 5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance

or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

### **Site Sign**

- F8. 1) A sign must be erected in a prominent position on the site
- a) stating that unauthorised entry to the work site is prohibited;
  - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
  - c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
- 2) Any such sign must be maintained while building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

### **G. Prior to the Issue of an Occupation Certificate**

#### **Infrastructure Repair and Completion of Works**

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
- a. in the road reserve must be fully completed; and
  - b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of public assets)

#### **Certification - Civil Works**

- G2. a) An appropriately qualified and practising Civil Engineer must certify to the Certifying Authority that the stormwater drainage system is constructed in accordance with this consent and the provisions of the applicable Australian Standard. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority) upon completion of the development works and prior to the issue of an Occupation Certificate.
- b) An appropriately qualified and practicing Civil Engineer must certify to the Certifying Authority that the vehicular crossing and associated works and road works were constructed in accordance with this consent and any approval for works in the road reserve issued by the Council. A copy of the certificate must be submitted to Council (if it is not the Certifying Authority), upon completion of the development works and prior to the issue of an Occupation Certificate.

(Reason: Compliance with the Consent)

#### **Damage to Adjoining Properties**

G3. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

#### **Utility Services**

G4. All utility services shall be adjusted to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

#### **Asbestos Clearance Certificate**

G5. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Certifying Authority (and a copy forwarded to Council if it is not the Certifying Authority) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following:

- a) the building/land is free of asbestos; or
- b) the building/land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

Note: Further details of licensed asbestos waste disposal facilities can be obtained from [www.epa.nsw.gov.au](http://www.epa.nsw.gov.au).

(Reason: To ensure that building works involving asbestos-based products are safe for occupation and will pose no health risks to occupants)

#### **Disposal Information**

G6. Upon completion of works and prior to occupation, a report including the following information must be provided to Council's Open Space and Environmental Services Department:

- (a) the total tonnage of all waste and excavated material disposed of from the site (including any tipping dockets); and
- (b) the disposal points and methods used.

(Reason: To ensure appropriate disposal methods are undertaken for auditing and inspection purposes)

**Height**

- G7. Upon completion of works and prior to the issue of any Occupation Certificate the RL of the development measured at 55.40 must be surveyed and certified by an appropriately qualified and practising surveyor as compliant with the maximum approved levels in accordance with the approved architectural drawings as contained in Condition A1 of this consent.

This survey and certification must be submitted to the Certifying Authority with the application for an Occupation Certificate and a copy provided to Council (if it is not the Certifying Authority.)

(Reason: To ensure compliance with the terms of this development consent)

**BASIX Completion Certificate**

- G8. In accordance with Clause 154C of the Environmental Planning and Assessment Regulation 2000, prior to issuing a final occupation certificate the Certifying Authority must apply to the Director-General for a BASIX completion receipt.

(Reason: To ensure compliance with the specified BASIX Certificate)

**Unpaved Verge**

- G9. The unpaved verge area must be constructed/reconstructed with an appropriate species of grass prior to completion of the works at no cost to Council.

(Reason: To ensure that community assets are presented in accordance with reasonable community expectations)

**Compliance with Certain Conditions**

- G10. Prior to the issue of any Occupation Certificate **Conditions C1 and C2** must be certified as having been implemented on site and complied with.

(Reason: To ensure the development is completed in accordance with the requirements of this consent)

***I. Ongoing/Operational Conditions***

**Single Occupancy**

- I1. Nothing in this consent authorises the use of the premises other than for a single occupancy.

(Reason: To ensure compliance with the terms of this consent)

**Maintenance of Approved Landscaping**

- I2. The owner of the premises at 5 Ryries Parade, Cremorne is to maintain the landscaping approved by this consent generally in accordance with Landscape Plan as modified by **Condition C2**.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

Should it be desired to substitute plants which are not of the same mature height, canopy density and nature (particularly flowering for non-flowering, native for exotic, deciduous for non-deciduous or the reverse of any these) a modification to this consent will be required.

(Reason: To ensure maintenance of the amenity, solar access and views of adjoining properties)