



The Trust Company (Australia) Limited as Trustee for 201 Miller Sub Trust
C/- LaSalle Investment Management
Level 16, 180 George Street
SYDNEY NSW 2000

D145/23
RW (CIS)

**ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED
NOTICE OF DETERMINATION – Approval**

Issued under Section 4.18 of the Environmental Planning and Assessment Act 1979 (“the Act”). Clause 87 of the Environmental Planning and Assessment Regulation 2021 (“the Regulation”)

Development Application Number: 145/23

Land to which this applies: 201 Miller Street, North Sydney
Lot No.: 1, DP: 706146

Applicant: The Trust Company (Australia) Limited as Trustee for 201 Miller Sub Trust C/- LaSalle Investment Management

Proposal: Replacement of existing window shrouds and repairs and maintenance of the façade of a 23-storey commercial building and heritage listed item.

Determination of Development Application: The development application was considered by the **North Sydney Local Planning Panel (NSLPP)** on 3 April 2024. Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, approval has been granted subject to conditions in the notice of determination.

Date of Determination: 3 April 2024

Reason for approval: The Panel supported the upgrading of the building in compliance with the standards. However, it was felt that the additional cost required by Condition A7 and likely aesthetic improvement was difficult to justify and therefore that condition was deleted.

Consent to operate from: 16 April 2024

Consent will lapse on: 16 April 2029

Period of Consent

Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite by 16 April 2029.

How community views were taken into account:

No submissions were received during the 14-day notification period with adjoining sites and the Stanton/CBD Precinct. The amended proposal is not required to be notified as per s3.6 of the North Sydney Community Participation Plan.


Review of determination and right of appeal:

Within 6 months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

Plans endorsed by the consent authority – please refer to condition A1

Endorsed for and on behalf of North Sydney Council

16/4/2024
DATE


Signature on behalf of consent authority
DAVID HOY
TEAM LEADER (ASSESSMENTS)

(i) **Conditions**

Consent is granted subject to the following conditions imposed pursuant to Section 4.18 of the Environmental Planning & Assessment Act 1979 (“the *Act*”) and the provisions of the Environmental Planning & Assessment Regulation 2021 (“the *Regulation*”) such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.18 of the Act.

(ii) **Definitions**

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act 1987* as in force at the date of consent.

Applicant means the applicant for this consent.

Approved Plans means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or ***AS/NZS*** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

NCC means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

Council means North Sydney Council.

Court means the Land and Environment Court.

Local Native Plants means species of native plant endemic to North Sydney LGA.

Stormwater Drainage System means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

Owner means the owner of the *site* and successors in title to the *site*.

Owner Builder has the same meaning as in the *Home Building Act 1989*.

Principal Certifier for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

Principal Contractor for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

Professional Engineer has the same meaning as in the *NCC*.

Public Place has the same meaning as in the *Local Government Act 1993*.

Road has the same meaning as in the *Roads Act 1993*.

SEE means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

Site means the land being developed subject to this consent.

NSLEP 2013 means *North Sydney Local Environmental Plan 2013*

NSDCP 2013 means *North Sydney Development Control Plan 2013*

Work for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: **Interpretation of Conditions** – Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

INDEX OF CONDITIONS

	Page No.
A. Conditions that Identify Approved Plans	
A1. Development in Accordance with Plans/documentation	7
A2. Plans on Site	8
A3. No Demolition of Extra Fabric	8
A4. External Finishes & Materials	8
A5. Statement of Significance and Ongoing Heritage Conservation Strategy	9
A6. Screening Plants	9
B. Matters to be Completed before the lodgement of an Application for a Construction Certificate	
B1. Construction Management Program – North Sydney Council Traffic Division Approval	9
C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)	
C1. Dilapidation Report Damage to Public Infrastructure	9
C2. Structural Adequacy of Existing Building	10
C3. Sediment Control	10
C4. Waste Management Plan	11
C5. Heritage Architect to be commissioned	11
C6. Reflectivity Index of Glazing	12
C7. Work Zone	12
C8. Maintain Property Boundary Alignment Levels	13
C9. Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	13
C10. Tree Bond for Public Trees	14
C11. Protection of Trees	14
C12. Asbestos & Hazardous Material Survey	15
C13. Construction Noise Management Plan	16
C14. Section 7.12 Development Contributions	17
C15. Security Deposit/ Guarantee Schedule	17
C16. Arborist to be Commissioned	18
C17. Tree Protection	18
D. Prior to the Commencement of any Works (and continuing where indicated)	
D1. Photographic Survey (Heritage Items)	19
D2. Protection of Trees	19
D3. Temporary Fences and Tree Protection	19
D4. Public Liability Insurance – Works on Public Land	20
D5. Asbestos Material Survey	20
D6. Commencement of Works' Notice	21
D7. Tree Protection	21
D8. Project Arborist Engaged	21
D9. Protection of Public Trees	22

E. During Demolition and Building Work

E1.	Road Reserve Safety	22
E2.	Temporary Disposal of Stormwater Runoff	23
E3.	Removal of Extra Fabric	23
E4.	Dust Emission and Air Quality	23
E5.	Noise and Vibration	23
E6.	Compliance with Construction Noise Management Plan	24
E7.	No Work on Public Open Space	24
E8.	Applicant's Cost of Work on Council Property	24
E9.	No Removal of Trees on Public Property	24
E10.	Protection of Trees	24
E11.	Construction Hours	25
E12.	Out of Hours Work Permits	25
E13.	Installation and Maintenance of Sediment Control	26
E14.	Site Amenities and Facilities	26
E15.	Health and Safety	27
E16.	Community Information	27
E17.	Prohibition on Use of Pavements	27
E18.	Plant & Equipment Kept Within Site	27
E19.	Waste Disposal	28
E20.	Asbestos Removal	28

F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation

F1.	National Construction Code	28
F2.	Appointment of a Principal Certifying Authority (PCA)	28
F3.	Construction Certificate	28
F4.	Occupation Certificate	29
F5.	Critical Stage Inspections	29
F6.	Commencement of Works	29
F7.	Excavation/Demolition	29
F8.	Protection of Public Places	29
F9.	Site Sign	30

G. Prior to the Issue of an Occupation Certificate

G1.	Infrastructure Repair and Completion of Works	30
G2.	Asbestos Clearance Certificate	31
G3.	Certification of Tree Condition	31
G4.	Verification Statement (External Finishes and Materials)	32

I. On-Going / Operational Conditions

I1.	Maintenance of Approved Landscaping	32
-----	-------------------------------------	----

A. Conditions that Identify Approved Plans

Development in Accordance with Plans/Documentation

A1. The development must be carried out in accordance with the following drawings endorsed with Council's approval stamp and other documentation listed in the table to this clause, or cited by other conditions, and as amended by other conditions of this consent.

Plan No.	Rev	Description	Prepared by	Dated
DA-00-02	1	Site Location Plan	Sissons Architects	20/4/2023
DA-00-04	1	Site Setout	Sissons Architects	20/4/2023
DA-00-05	2	Scoping Plans & Elevations	Sissons Architects	14/2/2024
DA-12-01	1	Typical GA Floor Plan (Levels L01-21)	Sissons Architects	20/4/2023
DA-20-01	2	GA Elevations – West (Demolition & Proposed)	Sissons Architects	14/2/2024
DA-20-02	2	GA Elevations – South (Demolition & Proposed)	Sissons Architects	14/2/2024
DA-20-03	2	GA Elevations – East (Demolition & Proposed)	Sissons Architects	14/2/2024
DA-20-04	2	GA Elevations – North (Demolition & Proposed)	Sissons Architects	14/2/2024
DA-30-01	1	GA Sections (Proposed)	Sissons Architects	20/4/2023
DA-40-01	2	Façade Types Elevation – West & South (Proposed)	Sissons Architects	14/2/2024
DA-40-02	2	Façade Types Elevation – East & North (Proposed)	Sissons Architects	14/2/2024
DA-40-11	2	Façade Type 01 - Detail	Sissons Architects	14/2/2024
DA-40-21	2	Façade Type 02 - Detail	Sissons Architects	14/2/2024
DA-40-31	1	Façade Type 03 - Detail	Sissons Architects	20/4/2023
DA-45-01	2	Material Board	Sissons Architects	14/2/2024
-	-	Façade Colours & Specifications	Sissons Architects	Received by Council 19/3/2024
DA-75-01	2	Render 01 – Miller Street (South East)	Sissons Architects	14/2/2024
DA-75-02	2	Render 02 – Miller Street (North East)	Sissons Architects	14/2/2024
BA6160	B	Construction Management Plan (CMP) – 201 Miller Street, North Sydney – Façade replacement works	Buildcorp	28/11/2022
-	B	Construction and Demolition Waste Management Plan	Elephants Foot Consulting P/L	2/12/2022
-	P3	JV3 Compliance Report Project 2 – Façade Upgrade	Erbas Associates P/L	6/12/2022
	1	Noise Impact Assessment	PWNA	3 November 2022

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

Plans on Site

- A2. A copy of all plans endorsed with Council's approval stamp, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifier.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the Principal Certifier upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

No Demolition of Extra Fabric

- A3. Alterations to, and demolition of the existing building shall be limited to that documented on the approved plans.

(Reason: To ensure compliance with the approved development)

External Finishes and Materials

- A4. External finishes and materials must be in accordance with the submitted schedule dated received by Council on 19 March 2024, unless otherwise modified by Council in writing by Council's Manager Development Services. Substitution of materials must not be undertaken, except where otherwise approved in writing by Council.

Window Shroud:

Interpon Powdercoat: Anodic Slate Grey YY218A

Grey Paint (Exterior Wall):

Dulux: S13A4 Mole Grey

Tinted Glass:

ASG Glass: 6mm Champagne 40-1 – On Clear + 12mm Argon + 6mm Clear

Visible Light Transmission (VLT): 37%

U-Value: 1.42

Solar Heat Gain Coefficient (SHGC): 0.23

External Reflectivity (ER): 10%

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

Statement of Significance and Ongoing Heritage Conservation Strategy

- A5. That the statement of significance relating to the subject heritage item be updated and that an overall heritage strategy for the site be devised incorporating the historical findings and works carried out to date to assist in the ongoing management of the site as well as establish an agreed set of exemptions to support its ongoing conservation. A copy of this report is to be submitted to Council for archival/record purposes.

(Reason: To ensure the ongoing protection and management of the heritage significance of the site)

Screening Plants

- A6. The empty planter bed containing dead stumps of past trees along the northern boundary of the subject site is to be planted with *Bambusa textilis* var 'Gracilis' (45L).

(Reason: To provide appropriate landscaping to enhance the aesthetics of the heritage building)

B Ancillary Matters to be Completed Prior to Issue of Construction Certificate

Construction Management Program –North Sydney Council Traffic Division Approval

- B1. A Construction Management Program must be prepared by a suitably qualified and experienced traffic consultant and submitted to and approved by the relevant North Sydney Council Traffic Engineer.

(Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the demolition process in a manner that respects adjoining owner's property rights and residential amenity in the locality, without unreasonable inconvenience to the community)

C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated)

Dilapidation Report Damage to Public Infrastructure

- C1. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the

development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Principal Certifier with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

Structural Adequacy of Existing Building

C2. A report prepared by an appropriately qualified and practising structural engineer, certifying the structural adequacy of the property and its ability to withstand the proposed additional, or altered structural loads during all stages of construction shall be submitted to the Principal Certifier for approval prior to issue of any Construction Certificate. The certified report must also include all details of the methodology to be employed in construction phases to achieve the above requirements. The methodology in the certified report must be complied with at all times.

(Reason: To ensure the structural integrity of the building is maintained)

Sediment Control

C3. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th Edition, Landcom, 2004) commonly referred to as the "Blue Book" or a suitable and effective alternative method.

An Erosion and Sediment Control Plan must be prepared and submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Erosion and Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

Waste Management Plan

C4. A Waste Management Plan is to be submitted for approval by the Principal Certifier prior to the issue of any Construction Certificate. The plan must include, but not be limited to:

- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
- b) The design of the on-site waste storage and recycling area; and
- c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

Heritage Architect to be commissioned

C5. An appropriately qualified and experienced heritage architect must be commissioned to assist the design development, contract documentation and overseeing of construction works on the site for their duration by undertaking regular inspections of the works in progress and providing advice in relation to heritage matters.

Written details of the engagement of the experienced heritage architect must be submitted to the Principal Certifier prior to the issue of any Construction Certificate.

Note: if advice provided by the heritage architect is to the effect that works requiring development consent be carried out, such works would require a Modification under s 4.55 of the *Environmental Planning and Assessment Act 1979* or further development application. This condition, and any advice given by the heritage architect, should not be construed as authorising the carrying of development with/ otherwise than in accordance with the development consent.

(Reason: To ensure that all matters relating to significant fabric and spaces are resolved and recorded using best practice for heritage conservation)

Reflectivity Index of Glazing

- C6. The glazing for windows, walls or roof finishes of the approved development must be factory pre-finished with low glare and reflectivity properties. Plans and specifications which comply with this condition must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Note: The reflectivity index of glazing elements can be obtained from glazing manufacturers. Glass with mirrored or reflective foil finishes is unlikely to achieve compliance with this requirement.

(Reason: To ensure that excessive glare or reflectivity nuisance from glazing does not occur as a result of the development)

Work Zone

- C7. If a Work Zone is required a Work Zone permit is to be obtained from Council prior to the issue of any Construction Certificate.

Note: For major development an application for work zone permit must be considered by the North Sydney Local Traffic Committee.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Works Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Works Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Principal Certifier to enable issue of the Construction Certificate. Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

Maintain Property Boundary Alignment Levels

- C8. Except where otherwise approved by Council, the property boundary alignment levels must match the levels which existed prior to the commencement of works. Plans and specifications which document existing and proposed levels adjacent to the site boundaries and which comply with the requirements of this condition must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate.

The Principal Certifier must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure interface between property and public land remains uniform)

Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement

- C9. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$250,000.00 to be held by Council for the payment of cost for any/all of the following:

- a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
- b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and [environmental controls](#)) required in connection with this consent
- c) remedying any defects in any such public work that arise within 6 months after the work is completed.
- d) Council reserves the right to retain all bonds on infrastructure works relating to the completion of required Infrastructure work for a 12-month defect liability period. Council may elect to provide a lesser period for minor residential work.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of six months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Development Engineers or Manager of Development Services.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following:

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;

- works in the public road associated with the development are to an unacceptable quality; and
- the Principal Certifier must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

Tree Bond for Public Trees

C10. Prior to the issue of any construction certificate, security in the sum of \$50,000.00 must be provided to Council for the protection of trees in public places, including the making good of any damage caused to such trees. The security is to be provided in accordance with the Schedule below.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate but only upon inspection and release by Council's Landscape Development Officer.

If any tree is removed or damaged Council may deduct from this security the reasonable cost of replacement with a tree of the same species and to a similar stage of growth it would have attained at the completion of the work.

In the case of any tree, which cannot be replaced with a similar specimen, the security for that tree will be forfeited to Council and used to provide replacement street plantings.

Schedule

Tree Species	Location	Bond
3x <i>Platanus sp.</i> (18m)	Council verge in front of 201-211 Miller Street	\$45,000
1x <i>Platanus sp.</i> (20m)	Council verge in front of 213 Miller Street (south)	\$5,000

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

Protection of Trees

C11. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Height
3x <i>Platanus sp.</i>	Council verge in front of 201-211 Miller St	To 18m
1x <i>Platanus sp.</i>	Council verge in front of 213 Miller St(sth)	20m
2 x <i>Phoenix canariensis</i>	Front setback 201-211 Miller St	To 18m
17 x <i>Magnolia 'Little Gem'</i>	Front setback 201-211 Miller St	To 12m
2 x <i>Juniperus sp.</i>	Front setback 201-211 Miller St	8m
10 x <i>XCupressocyparis leylandii</i>	Front setback 201-211 Miller St	To 12m
<i>Buxus hedging</i>	Front setback 201-211 Miller St	To 1m

Scaffolding and hoarding shall be optimised to minimise impact to protected trees and reduce need for any pruning.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

Asbestos and Hazardous Material Survey

C12. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Principal Certifier as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily)

Construction Noise Management Plan

C13. A Construction Noise Management Plan must be prepared by an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants, and must include the following:

- (a) Identification of noise affected receivers near to the site.
- (b) A prediction as to the level of noise impact at noise affected receivers from the use and proposed number of high noise intrusive appliances intended to be operated onsite.
- (c) Details of work schedules for all construction phases.
- (d) A statement should also be submitted outlining whether or not predicted noise levels will comply with the noise criteria stated within the Environment Protection Authority's Construction Noise Guideline.
- (e) Representative background noise levels should be submitted in accordance with the ICNG.
- (f) Confirmation of the level of community consultation that is to be undertaken by occupants at noise affected receivers likely to be most affected by site works and the operation of plant/machinery particularly during the demolition and excavation phases.
- (g) Confirmation of noise monitoring methodology that is to be undertaken during the noise intensive stages of work including details of monitoring to be undertaken at the boundary of any noise affected receiver.
- (h) What course of action will be undertaken following receipt of a complaint concerning offensive noise.
- (i) Details of any noise mitigation measures that have been outlined by an acoustic consultant or otherwise that will be deployed on site to reduce noise impacts on the occupants at noise affected receivers.
- (j) Details of selection criteria for any plant or equipment that is to be used on site, the level of sound mitigation measures to be undertaken in each case and the criteria adopted in their selection taking into account the likely noise impacts on occupants at noise affected receivers and other less intrusive technologies available; and
- (k) Details of site induction to be carried out for all employees and contractors undertaking work at the site.

"affected receiver" includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

"boundary" includes any window or elevated window of an affected residence.

The Construction Noise Management Plan must be submitted to the Principal Certifier and a copy provided to Council prior to the issue of the Construction Certificate.

(Reason: To ensure noise generating activities are appropriately managed and nearby sensitive receivers protected)

Section 7.12 Development Contributions

C14. A monetary contribution pursuant to the provisions of Section 7.12 of the Environmental Planning and Assessment Act 1979 is to be paid to Council, in accordance with the North Sydney Council's Contribution Plan, to provide for local infrastructure improvements.

Based on the cost of development at the date of determination, the total contribution payable to Council is \$181,916.00.

Indexation

The monetary contribution required under this consent will be indexed between the date of the grant of the consent and the date on which the contribution is paid the time of payment in accordance with quarterly movements in the Consumer Price Index (All Groups Index) for Sydney as published by the Australian Bureau of Statistics.

Timing of payment

The contribution must be paid to Council prior to issue of any Construction Certificate for any work approved by this consent.

A copy of the North Sydney Contribution Plan can be viewed at North Sydney Council's Customer Service Centre, 200 Miller Street, North Sydney or downloaded via Council's website at www.northsydney.nsw.gov.au

(Reason: To provide for local infrastructure identified in the North Sydney Council Local Contributions Plan 2020)

Security Deposit/Guarantee Schedule

C15. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

Security Deposit/Guarantee	Amount (\$)
Street Tree Bond	\$50,000.00
Infrastructure Damage Bond	\$250,000.00
TOTAL BONDS	\$300,000.00

Note: The following fees applicable

Fees	
Local Infrastructure Contributions	\$181,916.00
TOTAL FEES	\$181,916.00

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

Arborist to be Commissioned

C16. An experienced AQF Level 5 consulting arborist must be commissioned to assist the design development, contract documentation and overseeing of construction works on the site for their duration by undertaking regular inspections of the works in progress and providing advice in relation to tree matters. The project arborist shall ensure design and construction of scaffolding/hoarding and tree protection is optimised to minimise impact to trees and reduce need for any pruning.

Written details of the engagement of the experienced arborist must be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

Note: This condition, and any advice given by the consulting arborist, should not be construed as authorising the carrying of development with/ otherwise than in accordance with the development consent.

(Reason: To ensure that all matters relating to trees are resolved and recorded using best practice.)

Tree Protection

- C17. To ensure the protection of all trees to be retained, the following measures are to be undertaken:
- a) All documentation for the Construction Certificate application must show the site trees to be retained, and retention of the adjoining trees, with their positions and diameters of trunks and crowns (canopies) to be clearly and accurately shown in relation to all levels of the proposed development.
 - b) All plans and correspondences must refer to the required compliance with the approved Tree Protection and Management Plan, and clearly show the assigned number of each tree on site, adjoining and Council land.
 - c) A Consulting Arboriculturist (“the project arboriculturist”), who holds a minimum Australian Qualification Framework Level 5 in Arboriculture, is a registered consulting member of a nationally recognised arboricultural organisation or association, and who does not remove or prune trees in the North Sydney local government area, shall be engaged before work commences for the duration of site preparation, demolition, construction and landscaping.

- d) The project arboriculturist shall inspect, monitor, supervise, provide recommendations and written reports and certification relating to protection of the trees and compliance with the conditions of consent.
- e) The contact details of the project arboriculturist shall be advised to council before work commences and maintained up to date for the duration of works. If a new project arborist is appointed details of the new project arborist shall be notified to council within 7 days.

(Reason: Tree protection measures)

D. Prior to the Commencement of any Works (and continuing where indicated)

Photographic Survey (Heritage Items)

- D1. Prior to any works commencing a photographic survey recording, in accordance with the NSW Heritage Office Guidelines "Photographic recording of Heritage Items using file or digital capture", is to be prepared to the satisfaction of Council's Historian and Conservation Planner. Two (2) copies of the photographic survey must be provided to Council.

(Reason: To provide a historical record of heritage significant fabric on site for archival purposes)

Protection of Trees

- D2. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provide to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

No canopy pruning to any protected tree shall be permitted.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

Temporary Fences and Tree Protection

- D3. All protected trees on-site that are specifically nominated as per Condition C11 *Protection of Trees* to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builder's waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites), not less than the distance shown in the schedule hereunder, must be installed to the satisfaction of the Principal Certifier prior to demolition or commencement of any works and must be maintained for the duration of the works: -

(Reason: To protect the trees to be retained on the site during construction works)

Public Liability Insurance – Works on Public Land

D4. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council’s road reserve or public land, as approved by this consent. The Policy is to note and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land.

Asbestos Material Survey

D5. Prior to the commencement of any works, a report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating “DANGER ASBESTOS REMOVAL IN PROGRESS” must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Principal Certifier as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Principal Certifier for approval prior to the issue of any Construction Certificate. The Principal Certifier must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long-term health of workers on site and occupants of the building is not put at risk unnecessarily)

Commencement of Works' Notice

D6. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least 2 days notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Tree Protection

D7. The tree protection measures detailed in the approved Tree Protection and Management Plan, and as directed by the project arboriculturist shall be established before work commences.

(Reason: To ensure that the stability and ongoing viability of trees being retained are not compromised Tree protection measures)

Project Arborist Engaged

- D8.
- The project arboriculturist shall inspect tree protection measures and certify in writing to the Principal Certifying Authority the measures comply with the approved Tree Protection Plan and as directed by the project arboriculturist before work commences.
 - The project arboriculturist shall provide guidance and oversight of tree protection and management to ensure that the stability and ongoing viability of trees being retained is not compromised.
 - The project arboriculturist must contact the tree pruning contractor and Council's Tree Management Officer (giving at least 2 working days' notice) to arrange a joint site meeting, prior to commencing any pruning, to determine the exact location and extent of pruning that is permissible, with the tree pruning contractor to comply with any instructions issued by Council, acting reasonably.
 - Any pruning must be undertaken by a practicing arborist with a minimum Australian Qualification Framework Level 3 in arboriculture, in accordance with the principles of the Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and the NSW Work Cover Code of Practice for the Amenity Tree Industry (1998), as well as any instructions issued on site by Council, acting reasonably.
 - The practicing arborist must keep a log of dates and times of when they attended the site, the type of works that were performed, and must form part of the certification required prior to Occupation.

(Reason: Tree protection measures)

Protection of Public Trees

- D9. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

Tree	Location	Protection
3x <i>Platanus sp.</i> (18m)	Council verge in front of 201-211 Miller St	Trunk, branch & root protection
1x <i>Platanus sp.</i> (20m)	Council verge in front of 213 Miller St (sth)	Trunk, branch & root protection

Trunk protection to be installed by first wrapping the stem of the tree in hessian or like material then strapping timber battens over the top. It is recommended that timber battens with the dimensions of length 2000mm, width 75mm and depth 50mm are used. The battens are not to be directly screwed or nailed into the tree.

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: Protection of existing environmental and community assets)

E. *During Demolition and Building Work*

Road Reserve Safety

- E1. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". **If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.**

(Reason: Public Safety)

Temporary Disposal of Stormwater Runoff

- E2. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Principal Certifier.

(Reason: Stormwater control during construction)

Removal of Extra Fabric

- E3. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

Dust Emission and Air Quality

- E4. The following must be complied with at all times:

- (a) Materials must not be burnt on the site.
- (b) Vehicles entering and leaving the site with soil or fill material must be covered.
- (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines - Managing Urban Stormwater: Soils and Construction.
- (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

Noise and Vibration

- E5. The works must be undertaken in accordance with the "Interim Construction Noise Guideline" published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

Compliance with Construction Noise Management Plan

E6. All works conducted on site which form part of this development must be carried out in accordance with the submitted Construction Noise Management Plan submitted with the Construction Certificate and all conditions of consent.

(Reason: To ensure noise generating activities are appropriately managed and nearby sensitive receivers protected)

No Work on Public Open Space

E7. No work can be undertaken within adjoining public lands (i.e., Parks, Reserves, Roads etc) without the prior written consent of Council. In this regard the developer is to liaise with Council prior to the commencement of any design works or preparation of a Construction and Traffic Management Plan.

(Reason: Protection of existing public infrastructure and land and to ensure public safety and proper management of public land)

Applicant's Cost of Work on Council Property

E8. The Applicant or the person, company or other entity that is acting upon this consent, must bear the cost of all works associated with the development that occurs on Council's property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

No Removal of Trees on Public Property

E9. No trees on public property (footpaths, roads, reserves, etc.) unless specifically approved by this consent shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works.

(Reason: Protection of existing environmental infrastructure and community assets)

Protection of Trees

E10. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009. All recommendations provided by the project arborist must be implemented for the duration of the works.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

Notes:

- a. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
- b. An application to modify this consent pursuant to Section 4.55 of the Environmental Planning and Assessment Act 1979 will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

Construction Hours (Commercial Core and Mixed-use Zones)

- E11. Construction activities and works approved under this consent must be restricted to within the hours stipulated in the following table:

Standard Construction Hours		
Location	Day	Hours
All other Zones	Monday - Friday	7.00am - 7.00pm
	Saturday	8.00am - 1.00pm
	Sunday Public holiday	No work permitted

Construction activities for development approved under this consent must be carried out in accordance with the standard construction hours above, the EPA Noise Policy for Industry 2017 and any Construction Noise Management Plan required under this consent.

In the event of breach to the approved hours of construction Council take may take enforcement action under Part 9 of the EP&A Act 1979 and in accordance with Council's adopted Compliance & Enforcement Policy.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

Out of hours' Work Permits

- E12. Where it is necessary for works to occur outside those hours allowed by these conditions, an application may be made to Council's Customer Services Centre for a permit to carry out works outside of the approved hours. If a permit is issued the works approved must be carried out in accordance with any requirements specified in the permit. Permits will only be approved if **public safety is at risk**. Applications which seek a variation to construction hours solely to benefit the developer will require the lodgement and favourable determination of a modification application pursuant to the provisions of Section 4.55 of the Environmental Planning and Assessment Act 1979.

Notes:

- 1) Failure to obtain a permit for work outside of the approved hours will result in on the spot fines being issued, or Council pursuing any action required (including legal proceedings) to have the out of hours work cease, without prior warning.
- 2) Applications for out of hour's works should be lodged with Council no later than seven (7) calendar days prior to the date of the intended works.
- 3) Examples of activities for which permits may be granted include:
 - the erection of awnings,
 - footpath, road and other infrastructure works which cannot be carried out for public convenience reasons within normal hours,
 - the erection and removal of hoardings and site cranes, and
 - craneage of materials which cannot be done for public convenience reasons within normal working hours.
- 4) Examples of activities for which permits WILL NOT be granted include:
 - extended concrete pours
 - works which are solely to convenience the developer or client, and
 - catch up works required to maintain or catch up with a construction schedule.
- 5) Further information on permits can be obtained from the Council website at www.northsydney.nsw.gov.au.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

Installation and Maintenance of Sediment Control

- E13. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils and Construction (4th Edition, Landcom, 2004), commonly referred to as the "Blue Book" and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

Site Amenities and Facilities

- E14. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work-place determines the type of amenities required.

Further information and details can be obtained from the Internet at www.workcover.nsw.gov.au

(Reason: To ensure the health and safety of the community and workers on the site)

Health and Safety

- E15. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at www.workcover.nsw.gov.au.

(Reason: To ensure the health and safety of the community and workers on the site)

Community Information

- E16. Reasonable measures must be undertaken at all times to keep nearby residents informed about the proposed work, such as by way of signs, leaflets, public meetings and telephone contact numbers, to ensure that adjoining residents are aware of the likely duration of the construction works on the site

(Reason: To ensure that residents are kept informed of activities that may affect their amenity)

Prohibition on Use of Pavements

- E17. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

Plant and Equipment Kept Within Site

- E18. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at www.northsydney.nsw.gov.au.

(Reason: To ensure public safety and amenity on public land)

Waste Disposal

E19. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

Asbestos Removal

E20. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or "Demolition Licence" and a current WorkCover "Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

F. *Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation*

National Construction Code

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

Appointment of Principal Certifying Authority (PCA)

F2. Building work, **demolition** or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifier for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Construction Certificate

F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Occupation Certificate

F4. A person must not commence occupation or use of the whole or any part of a new building (new building includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifier appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

Critical Stage Inspections

F5. Building work must be inspected by the Principal Certifier on the critical stage occasions prescribed by the EP&A Act and its Regulations, and as directed by the appointed Principal Certifier.

(Reason: Statutory)

Commencement of Works'

F6. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least two days' notice to North Sydney Council of the person's intention to commence the erection of the building.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

Excavation/Demolition

- F7. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
- 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
- 3) Demolition work must be undertaken in accordance with the provisions of AS2601-Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

Protection of Public Places

- F8. 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
- 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

- 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
- 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
- 5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

Site Sign

- F9.
- 1) A sign must be erected in a prominent position on the site
 - a) stating that unauthorised entry to the work site is prohibited;
 - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
 - c) showing the name, address and telephone number of the Principal Certifier for the work.
 - 2) Any such sign must be maintained while to building work or demolition work is being carried out but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

G. Prior to the Issue of an Occupation Certificate

Infrastructure Repair and Completion of Works

- G1. Prior to the issue of any Occupation Certificate any and all works relating to the development:
- a. in the road reserve must be fully completed; and
 - b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council. Council's development engineer must be contacted to arrange inspections of the completed works in the Public Domain.

(Reason: Maintain quality of Public assets)

Asbestos Clearance Certificate

G2. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Principal Certifier (and a copy forwarded to Council if it is not the Principal Certifier) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following: -

- a) the building/ land is free of asbestos; or
- b) the building/ land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

Note: Further details of licensed asbestos waste disposal facilities can be obtained from www.epa.nsw.gov.au

(Reason: To ensure that building works involving asbestos based products are safe for occupation and will pose no health risks to occupants)

Certification of Tree Condition

G3. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Principal Certifier, describing the health of the tree(s) specifically nominated below: -

Tree	Location	Height
3x <i>Platanus sp.</i>	Council verge in front of 201-211 Miller St	To 18m
1x <i>Platanus sp.</i>	Council verge in front of 213 Miller St(sth)	20m
2 x <i>Phoenix canariensis</i>	Front setback 201-211 Miller St	To 18m
17 x <i>Magnolia 'Little Gem'</i>	Front setback 201-211 Miller St	To 12m
2 x <i>Juniperus sp.</i>	Front setback 201-211 Miller St	8m
10 x <i>XCupressocyparis leylandii</i>	Front setback 201-211 Miller St	To 12m
<i>Buxus hedging</i>	Front setback 201-211 Miller St	To 1m

The report must detail the condition and health of the nominated tree(s) upon completion of the works, and shall certify that the tree(s) has/have not been significantly damaged during the works on the site, and has/have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

Verification Statement (External Finishes and Materials)

- G4. Prior to the issue of any Occupation Certificate, a verification statement from a qualified designer or architect (preferably the original designer), must be submitted to Council and the Principal Certifier certifying that the external finishes and materials are in accordance with the approved schedule of finishes and materials identified in this consent.

“qualified designer” means a person registered as an architect in accordance with the Architects Act 2003 cf 50(1A) EP & A Regs 2000.

(Reason: To ensure the design quality and finishes for residential flat development)

I. On-Going / Operational Conditions

Maintenance of Approved Landscaping

- I1. The owner of the premises at 201 Miller Street, North Sydney is to maintain the landscaping approved by this consent.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

Should it be desired to substitute plants which are not of the same mature height, canopy density and nature (particularly flowering for non-flowering, native for exotic, deciduous for non-deciduous or the reverse of any these) a modification to this consent will be required.

(Reason: To ensure maintenance of the amenity, solar access and views of adjoining properties)