

Original signed by Robyn Pearson on 4/5/2020

Date determined: 24/4/2020

Date operates: 4/5/2020

Date lapses: 4/5/2025

SCECGS Redlands Limited  
C/- Urbis  
**Attention: Shaun de Smeth**  
Level 8, 123 Pitt Street  
SYDNEY NSW 2000

D381/19  
LK (CIS)

**ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 AS AMENDED**  
**NOTICE OF DETERMINATION – Approval**

---

**Development Application Number:** 381/19

---

**Land to which this applies:** 2-4 Winnie Street, & 3 Monford Place, Cremorne  
Lot No.: 33, DP: 537701

---

**Applicant:** SCECGS Redlands Limited, C/- Urbis

---

**Proposal:** Change of use of the site to an educational establishment, relocation of existing modular classrooms onto the site, associated civil and landscaping works, and use of the classrooms from 8am till 5pm, Monday to Fridays.

---

**Determination of Development Application:** Subject to the provisions of Section 4.17 of the Environmental Planning and Assessment Act 1979, approval has been granted subject to conditions in the notice of determination.

---

**Date of Determination:** 24 April 2020

---

**Reason for approval:** The development application has been assessed against the North Sydney Local Environmental Plan 2013, the North Sydney Development Control Plan 2013, other Council policies and the relevant State Planning Policies.

The subject site is zoned R4 (High Density Residential), which is a prescribed zone for the purposes of SEPP (Educational Establishments and Child Care Facilities) 2017 and consequently development for the purpose of a school is permissible on the site with consent under the SEPP.

---

---

The design quality of the development has been evaluated in accordance with the design quality principles set out in Schedule 4 of SEPP (Educational Establishments and Child Care Facilities) 2017 and was found to be generally acceptable.

Whilst the provisions of the North Sydney Development Control Plan 2013 are of no effect as stated within Part 4, Clause 35(9) of SEPP (Educational Establishments and Child Care Facilities) 2017, the proposed development has been assessed on merit and consideration has been given to the performance of the proposal against the relevant controls. It is concluded that the proposal is generally acceptable given its temporary nature, and unlikely to give rise to undue amenity impacts for the adjoining properties.

Having regard to the provisions of Section 4.15 of the EP&A Act 1979 the application is considered to be satisfactory and is therefore recommended for **approval** subject to conditions of consent.

---

**Consent to operate from:** 4 May 2020

---

**Consent will lapse on:** 4 May 2025

---

**Period of Consent**

Subject to Section 4.20 of the Act, this consent becomes effective and operates from the date listed above. The consent lapses five years after the date of consent in accordance with Section 4.53 of the Act and cannot be extended. To activate this consent, works must physically commence onsite by 4 May 2025

---

**How community views were taken into account:**

The proposal was notified and advertised in accordance with the North Sydney Council Community Engagement Protocol. Notification of the original application attracted two submissions raising particular concern regarding noise from students and plant, loss of visual privacy, construction phase impacts and site isolation.

Notification of the revised plans attracted one further submission from a previous submitter, who reiterated their previous concerns, and who also considered the re-notification period was inadequate given the current health crisis. The issues raised in this further submission have been considered in the assessment of this application and are considered reasonable subject to conditions where appropriate to address the issues raised.

---

---

**Review of determination and right of appeal:**

Within 6 months after the date of notification of the decision, a review of this determination can be requested under Division 8.2 of the Act or an appeal to the Land and Environment Court made pursuant to the provisions of Section 8.7 of the Act. A review of determination should be lodged as soon as possible, and preferably no later two months after the date of notification of the decision to enable the review to be completed within the six-month period.

---

Plans endorsed by the consent authority – please refer to condition A1.

**Endorsed for and on behalf of North Sydney Council**

---

DATE

---

Signature on behalf of consent authority  
ROBYN PEARSON  
**TEAM LEADER (ASSESSMENTS)**

---

**(i) Conditions**

Consent is granted subject to the following conditions imposed pursuant to Section 4.17 of the Environmental Planning & Assessment Act 1979 (“the *Act*”) and the provisions of the Environmental Planning & Assessment Regulation 2000 (“the *Regulation*”) such conditions being reasonable and relevant to the development as assessed pursuant to Section 4.17 of the Act.

**(ii) Definitions**

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act* 1987 as in force at the date of consent.

***Applicant*** means the applicant for this consent.

***Approved Plans*** means the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

***AS*** or ***AS/NZS*** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

***NCC*** means the National Construction Code as published by the Australian Building Codes Board as in force at the date of issue of any *Construction Certificate*.

***Council*** means North Sydney Council.

***Court*** means the Land and Environment Court.

***Local Native Plants*** means species of native plant endemic to North Sydney LGA.

***Stormwater Drainage System*** means all works, facilities and documentation relating to:

- The collection of stormwater,
- The retention of stormwater,
- The reuse of stormwater,
- The detention of stormwater,
- The controlled release of stormwater; and
- Connections to easements and public stormwater systems.

***Owner*** means the owner of the *site* and successors in title to the *site*.

***Owner Builder*** has the same meaning as in the *Home Building Act* 1989.

***Principal Certifier*** for building or subdivision work means the certifier appointed as the principal certifier for the building work under section 6.6 (1) or for the subdivision work under section 6.12 (1).

**Principal Contractor** for building work means the person responsible for the overall coordination and control of the carrying out of the building work.

Note: If any residential building work is involved, the principal contractor must be the holder of a contractor licence under the *Home Building Act 1989*.

**Professional Engineer** has the same meaning as in the *NCC*.

**Public Place** has the same meaning as in the *Local Government Act 1993*.

**Road** has the same meaning as in the *Roads Act 1993*.

**SEE** means the final version of the Statement of Environmental Effects lodged by the *Applicant*.

**Site** means the land being developed subject to this consent.

**NSLEP 2013** means *North Sydney Local Environmental Plan 2013*

**NSDCP 2013** means *North Sydney Development Control Plan 2013*

**Work** for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of any waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an *occupation certificate*.

Note: **Interpretation of Conditions** – Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.

**INDEX OF CONDITIONS**

	<b>Page No.</b>
<b>A. <i>Conditions that Identify Approved Plans</i></b>	
A1. Time-limited Consent	9
A2. Development in Accordance with Plans/documentation	9
A3. Plans on Site	9
A4. External Finishes & Materials	10
<b>B. <i>Matters to be Completed before the lodgement of an Application for a Construction Certificate</i></b>	
B1. Construction Management Program – Local Traffic Committee Approval	10
<b>C. <i>Prior to the Issue of a Construction Certificate (and ongoing, where indicated)</i></b>	
C1. Noise from Plant and Equipment	11
C2. Stormwater Management and Disposal Design Plan – Construction Issue	12
C3. Tree Protection	12
C4. Additional Soft Landscaping	13
C5. Dilapidation Report Damage to Public Infrastructure	14
C6. Dilapidation Survey Private Property (Neighbouring Buildings)	14
C7. Sediment Control	15
C8. Waste Management Plan	15
C9. Roofing Materials - Reflectivity	16
C10. Work Zone	16
C11. Maintain Property Boundary Alignment Levels	16
C12. On-Site Stormwater Detention	17
C13. Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement	17
C14. Tree Bond for Public Trees	18
C15. Protection of Trees	19
C16. Approval for removal of Trees	19
C17. Pruning of Trees	20
C18. Asbestos Material Survey	20
C19. Screen Planting	21
C20. Security Deposit/ Guarantee Schedule	21
C21. Pruning of Trees	21
<b>D. <i>Prior to the Commencement of any Works (and continuing where indicated)</i></b>	
D1. Project Arborist to be Engaged	22
D2. Protection of Public Trees	22
D3. Property Boundary Fencing	23
D4. Protection of Trees	23
D5. Temporary Fences and Tree Protection	23
D6. Public Liability Insurance – Works on Public Land	24
D7. Sydney Water Approvals	24
D8. Commencement of Works Notice	24

***E. During Demolition and Building Work***

E1.	Service Adjustments	25
E2.	Cigarette Butt Receptacle	25
E3.	Parking Restrictions	25
E4.	Road Reserve Safety	25
E5.	Temporary Disposal of Stormwater Runoff	26
E6.	Removal of Extra Fabric	26
E7.	Dust Emission and Air Quality	26
E8.	Noise and Vibration	27
E9.	Developer's Cost of Work on Council Property	27
E10.	No Removal of Trees on Public Property	27
E11.	Protection of Trees	27
E12.	Special Permits	28
E13.	Construction Hours	29
E14.	Installation and Maintenance of Sediment Control	29
E15.	Sediment and Erosion Control Signage	29
E16.	Site Amenities and Facilities	30
E17.	Health and Safety	30
E18.	Prohibition on Use of Pavements	30
E19.	Plant & Equipment Kept Within Site	30
E20.	Waste Disposal	31
E21.	Asbestos Removal	31

***F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation***

F1.	National Construction Code	31
F2.	Home Building Act	31
F3.	Appointment of a Principal Certifier (previously known as a PCA)	32
F4.	Construction Certificate	32
F5.	Occupation Certificate	32
F6.	Excavation/Demolition	32
F7.	Protection of Public Places	33
F8.	Site Sign	33

***G. Prior to the Issue of an Occupation Certificate***

G1.	Noise Certification	34
G2.	Infrastructure Repair and Completion of Works	34
G3.	Damage to Adjoining Properties	34
G4.	Utility Services	34
G5.	Covenant & Restriction (Stormwater Control Systems)	34
G6.	Asbestos Clearance Certificate	35
G7.	Certification of Tree Condition	36
G8.	Landscaping	36
G9.	Compliance with Certain conditions	36

***I. On-Going / Operational Conditions***

I1.	Noise and Vibration	36
I2.	Classroom use	37
I3.	Hours of Operation	37
I4.	Ongoing Street Tree Care	37
I5.	Maintenance of Approved Landscaping	37



**A. Conditions that Identify Approved Plans**

**Time-limited Consent**

- A1. This consent shall cease on the expiration of 5 years after the date on which the consent becomes effective and operates in accordance with Part 4.20 of the Environmental Planning and Assessment Act 1979 (as amended).

Should the owner of the site wish to extend this period, a new development application shall be lodged with Council prior to the cessation of this consent, and preferably no later than three months prior to the cessation of this consent to enable adequate time for assessment prior to the lapsing of this consent.

(Reason: This application has been submitted and assessed as a temporary use within temporary buildings)

**Development in Accordance with Plans/documentation**

- A2. The development must be carried out in accordance with the following drawings and documentation and endorsed with Council's approval stamp, except where amended by the following conditions of this consent.

Drawing No.	Revision	Title	Drawn by	Dated
AR.DA.1105	C	Pedestrian and Vehicular Movement Diagram	TKD Architects	12/03/2020
AR.DA.1106	C	Site Plan	TKD Architects	12/03/2020
AR.DA.2001	C	Demolition Plan	TKD Architects	12/03/2020
AR.DA.2002	C	Ground Floor Plan	TKD Architects	12/03/2020
AR.DA.2003	C	Roof Plan	TKD Architects	12/03/2020
AR.DA.3001	C	Street Elevation	TKD Architects	12/03/2020
AR.DA.3002	C	Elevations	TKD Architects	12/03/2020
AR.DA.8001	C	Perspective Views	TKD Architects	12/03/2020
AR.DA.8002	A	External Materials	TKD Architects	19/11/2019
L-01	B	Landscape Plan	SILK	11/02/2020

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

**Plans on Site**

- A3. A copy of all stamped approved plans, specifications and documents (including the plans, specifications and documents submitted and approved with the Construction Certificate) must be kept on site at all times so as to be readily available for perusal by any officer of Council or the Principal Certifying Authority.

All documents kept on site in accordance with this condition must be provided to any officer of the Council or the certifying authority upon their request.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information and to ensure ongoing compliance)

### **External Finishes & Materials**

A4. External finishes and materials shall be in accordance with those shown within the approved plans listed in Condition A1 of this consent unless otherwise modified by Council in writing.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council, Public Information)

### ***B. Matters to be Completed before the lodgement of an Application for a Construction Certificate***

#### **Construction Management Program – Local Traffic Committee Approval**

B1. A Construction Management Program prepared by a suitably qualified and experienced traffic consultant must be submitted and approved in writing by North Sydney Traffic Committee PRIOR TO THE ISSUE OF ANY Construction Certificate. Any use of Council property will require appropriate approvals prior to any work commencing. At a minimum, the Construction Management Program must specifically address the following matters:

- a) A plan view (min 1:100 scale) of the entire site and frontage roadways indicating:
  - i. Dedicated temporary construction site driveway entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways and footways;
  - ii. The proposed signage for pedestrian management to comply with the relevant Australian Standards, including pram ramps;
  - iii. Turning areas within the site for construction and spoil removal vehicles, allowing a forward egress for all construction vehicles on the site;
  - iv. The locations of any proposed Work Zones in the frontage roadways (to be approved by Council's Traffic Committee);
  - v. Locations of hoardings proposed;
  - vi. Location of any proposed crane standing areas;
  - vii. A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
  - viii. Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected; and
  - ix. The provision of an on-site parking area for employees, tradesperson and construction vehicles as far as possible.
- b) A detailed heavy vehicle access route map through the Council area to Arterial Roads. Provision is to be made to ensure through traffic is maintained at all times.
- c) The proposed phases of works on the site, and the expected duration of each phase.
- d) How access to neighbouring properties will be maintained at all times and the proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of process.
- e) The road is not to be used as a waiting area for trucks delivering to or awaiting pick up of materials.

- f) The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising structural engineer and must not involve any permanent or temporary encroachment onto Council's property.
- g) Proposed protection for Council and adjoining properties. Details are to include site fencing and the provision of "B" class hoardings over footpaths and laneways.
- h) A Waste Management Plan. The Waste Management Plan must include, but not be limited to, the estimated volume of waste and method of disposal for the construction and operation phases of the development, design of on-site waste storage and recycling area and administrative arrangements for waste and recycling management during the construction process.

All traffic control work and excavation, demolition and construction activities must be undertaken in accordance with the approved Construction Management Program and any conditions attached to the approved Program. A certificate of compliance with this condition must be obtained from Council's development engineers. The certificate and the approved Construction Management Program must be submitted as part of the documentation lodged with the application for approval of a construction certificate. A copy of the approved Construction Management Program and any conditions imposed on that Program, must be kept on the site at all times and made available to any officer of Council upon request.

Notes:

- 1) North Sydney Council's adopted fee for certification of compliance with this condition shall be payable on lodgement, or in any event, prior to the issue of the relevant approval.
- 2) Any use of Council property will require appropriate approvals and demonstration of liability insurances prior to such work commencing.
- 3) Failure to provide complete and detailed information may result in delays. It is recommended that your Construction Management Plan be lodged with Council as early as possible, as a minimum six (6) weeks notice is required to refer items to the Traffic Committee.
- 4) Dependent on the circumstances of the site, Council may request additional information to that detailed above.

(Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the demolition process in a manner that respects adjoining owner's property rights and residential amenity in the locality, without unreasonable inconvenience to the community)

***C. Prior to the Issue of a Construction Certificate (and ongoing, where indicated).***

**Noise from Plant and Equipment**

C1. The use of all plant and equipment installed on the premises must not:

- (a) Contribute an LAeq(15min) which will cause the total LAeq(15min) from all plant and equipment operating contemporaneously on the site or in the strata scheme or in the mixed strata schemes to exceed the RBL by more than 5dB when measured at the boundary of any affected receiver. The modifying factor adjustments in Section 4 of the EPA Industrial Noise Policy shall be applied.

- (b) Cause “offensive noise” as defined in the *Protection of the Environment Operations Act 1997*.

“affected receiver” includes residential premises (including any lot in the strata scheme or another strata scheme), premises for short-term accommodation, schools, hospitals, places of worship, commercial premises and parks and such other affected receiver as may be notified by the Council in writing.

“boundary” includes any window or elevated window of an affected receiver.

Terms in this condition have the same meaning as in the Noise Guide for Local Government and the Industrial Noise Policy published by the NSW Environment Protection Authority.

(Reason: To maintain an appropriate level of amenity for adjoining land uses)

### **Stormwater Management and Disposal Design Plan – Construction Issue**

- C2. Prior to issue of the Construction Certificate, the applicant shall have a site drainage management plan prepared by a qualified drainage design engineer. The site drainage management plan must detail the following requirements of North Sydney Council:

- a) Compliance with BCA drainage requirements, Councils Engineering Performance guide and current Australian Standards and guidelines, such as AS/NZ3500.3.2 1998, National Plumbing and Drainage Code.
- b) Stormwater runoff and subsoil drainage generated by the approved dwellings must be conveyed in a controlled manner by gravity towards Council’s stormwater system in Monford Place.
- c) All redundant stormwater pipelines within the footpath area shall be removed and the footpath and kerb reinstated.
- d) All sub-soil seepage drainage shall be discharged via a suitable silt arrester pit. Details of all plans certified as being adequate for their intended purpose and compliant with the provisions of AS3500.3.2 by an appropriately qualified and practising civil engineer, shall be submitted with the application for a Construction Certificate.

Details demonstrating compliance are to be submitted with the Construction Certificate.

The Certifying Authority issuing the Construction Certificate must ensure that the approved drainage plan and specifications, satisfying the requirements of this condition, is referenced on and accompanies the Construction Certificate.

(Reason: To ensure controlled stormwater management and disposal without nuisance)

### **Tree Protection**

- C3. To ensure the protection of all trees to be retained, the following measures are to be undertaken:

- a) All documentation for the Construction Certificate application must show the site trees to be retained, and retention of the adjoining trees, with their positions and diameters of trunks and crowns (canopies) to be clearly and accurately shown in relation to all levels of the proposed development.

- b) All plans and correspondences must refer to the required compliance with the arborist report prepared by Redgum Horticultural dated 10.3.20 and clearly show the assigned number of each tree on the site, and on adjoining and Council land. The pruning of selected branches of Tree 1 *Cedrus deodar* as depicted in Section 14 of the arborist report prepared by Redgum Horticultural dated 10.3.20, shall be permitted in order to facilitate this proposal, but no other pruning to this tree shall be permitted.
- c) A Consulting Arboriculturist (“the project arboriculturist”), who holds a minimum Australian Qualification Framework Level 5 in Arboriculture, is a registered consulting member of a nationally recognised arboricultural organisation or association, and who does not remove or prune trees in the North Sydney local government area, shall be engaged before work commences for the duration of site preparation, demolition, construction and landscaping.
- d) The project arboriculturist shall inspect, monitor, supervise, provide recommendations and written reports and certification relating to protection of the trees and compliance with the conditions of consent.
- e) The contact details of the project arboriculturist shall be advised to council before work commences and maintained up to date for the duration of works. If a new project arborist is appointed details of the new project arborist shall be notified to council within 7 days.
- f) The project arboriculturist is to submit a list of critical stages where joint site inspections with Council’s Tree Management Officer will be required, with the adopted schedule to be complied with during the course of works, and include at minimum, the following hold points:
  - 1. Prior to demolition of existing structures;
  - 2. At commencement of any excavation works within 7 metres of any tree to be retained;
  - 3. Prior to any tree crown or root pruning;
  - 4. At commencement of construction works within 7 metres of any tree to be retained.

(Reason: Tree protection measures).

#### **Additional Soft Landscaping**

- C4. Additional soft landscaping (such as grass, ground covers, trees and/or shrubs) must be provided (total of 6% of the site area/65m<sup>2</sup>) after the removal of the eastern path (at the corner of classroom 6) and the southern pathway adjacent to classroom nos. 4,5,6 and the outer edges of the southern part of the deck near the ramp to/from Monford Place as shown in red on the approved plans.

(Reason: To provide additional soft landscaping and improve the environmental performance of the development)

### **Dilapidation Report Damage to Public Infrastructure**

- C5. A dilapidation survey and report (including photographic record) must be prepared by a suitably qualified consultant which details the pre-developed condition of the existing public infrastructure in the vicinity of the development site. Particular attention must be paid to accurately recording any pre-developed damaged areas so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development. A copy of the dilapidation survey and report is to be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The developer may be held liable for all damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded and demonstrated as pre-existing under the requirements of this condition.

The developer shall bear the cost of carrying out works to restore all public infrastructure damaged as a result of the carrying out of the development, and no occupation of the development shall occur until damage caused as a result of the carrying out of the development is rectified.

A copy of the dilapidation survey and report must be lodged with North Sydney Council by the Certifying Authority with submission of the Construction Certificate documentation.

(Reason: To record the condition of public infrastructure prior to the commencement of construction)

### **Dilapidation Survey Private Property (Neighbouring Buildings)**

- C6. A photographic survey and dilapidation report of adjoining property at No. 2A Winnie Street, detailing the physical condition of that property, both internally and externally, including, but not limited to, such items as walls, ceilings, roof, structural members and other similar items, SHALL BE submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The survey and report is to be prepared by an appropriately qualified person agreed to by both the applicant and the owner of the adjoining property. A copy of the report is to be provided to Council, if Council is not the Certifying Authority, prior to the issue of any Construction Certificate.

All costs incurred in achieving compliance with this condition shall be borne by the person entitled to act on this Consent.

In the event that access for undertaking the photographic survey and dilapidation report is denied by an adjoining owner, the applicant MUST DEMONSTRATE, in writing, to the satisfaction of Council that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed. Written concurrence must be obtained from Council in such circumstances.

Note: This documentation is for record keeping purposes only, and may be used by an applicant or affected property owner to assist in any action required to resolve any dispute over damage to adjoining properties arising from the works. It is in the applicant's and adjoining owner's interest for it to be as full and detailed as possible.

(Reason: Proper management of records)

### **Sediment Control**

- C7. Where construction or excavation activity requires the disturbance of the soil surface or existing vegetation, erosion and sediment control techniques, as a minimum, are to be in accordance with the publication *Managing Urban Stormwater: Soils & Construction* (4th edition, Landcom, 2004) commonly referred to as the “Blue Book” or a suitable and effective alternative method.

A Sediment Control Plan must be prepared and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate and prior to any works commencing. The Sediment Control Plan must be consistent with the Blue Book and disclose:

- a) All details of drainage to protect and drain the site during the construction processes;
- b) All sediment control devices, barriers and the like;
- c) Sedimentation tanks, ponds or the like;
- d) Covering materials and methods; and
- e) A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- f) Methods for the temporary and controlled disposal of stormwater during construction.

All works must be undertaken in accordance with the approved Sediment Control plan.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

### **Waste Management Plan**

- C8. A Waste Management Plan is to be submitted for approval by the Certifying Authority prior to the issue of any Construction Certificate. The plan must include, but not be limited to:

- a) The estimated volume of waste and method of disposal for the construction and operation phases of the development;
- b) The design of the on-site waste storage and recycling area; and
- c) Administrative arrangements for waste and recycling management during the construction process.

The approved Waste Management Plan must be complied with at all times in the carrying out of the development.

(Reason: To encourage the minimisation of waste and recycling of building waste)

### **Roofing Materials - Reflectivity**

- C9. Roofing materials must be factory pre-finished with low glare and reflectivity properties to be compatible with the colours of neighbouring buildings. The selected roofing material must not cause a glare nuisance or excessive reflectivity to adjoining or nearby properties. Plans and specifications which comply with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that excessive glare or reflectivity nuisance from roofing materials does not occur as a result of the development)

### **Work Zone**

- C10. If a Work Zone is proposed, an application must be made to the North Sydney Local Traffic Committee to install the 'Work Zone'. A Work Zone permit is required to be issued by the Council prior to the issue of any Construction Certificate.

Work Zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Work Zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site. If the Work Zone is approved by the Committee, the Applicant must obtain a written copy of the related resolution from the North Sydney Local Traffic Committee and submit a copy of this to the Certifying Authority to enable issue of the Construction Certificate.

Where approval of the 'Work Zone' is given by the Committee, the requirements of the Committee, including installation of the necessary 'Work Zone' signage and payment of any fees, must occur prior to commencement of any works on the site. Further, at the expiration of the Work Zone approval, the developer is required to remove the Work Zone signs and reinstate any previous signs, all at the developer's cost. The requirements imposed by the Committee on the Work Zone permit (or permits) must be complied with at all times.

(Reason: Amenity and convenience during construction)

### **Maintain Property Boundary Alignment Levels**

- C11. Except where otherwise approved by Council, the property boundary alignment levels must match the levels which existed prior to the commencement of works. Plans and specifications which document existing and proposed levels adjacent to the site boundaries and which comply with the requirements of this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure interface between property and public land remains uniform)



### **On-Site Stormwater Detention**

- C12. On site detention must be provided to ensure that the maximum discharge from the site does not exceed discharge which would occur during a 1 in 5 year storm for the time of concentration determined for the particular site, for the existing site conditions. All other stormwater run-off from the site for all storms up to the 1 in 100 year storm is to be retained on the site for gradual release to the kerb and gutter or drainage system. Provision is to be made for satisfactory overland flow should a storm in excess of the above parameters occur.

Determination of the required cumulative storage must be based on the mass curve technique as detailed in Technical Note 1, Chapter 14 of the Australian Rainfall and Runoff Volume 1, 1987 Edition.

Engineering calculations, design and certification complying with this condition must be provided by an appropriately qualified and practicing Civil Engineer and submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure that public infrastructure in Council's care and control is not overloaded)

### **Bond for Damage and Completion of Infrastructure Works – Stormwater, Kerb and Gutter, Footpaths, Vehicular Crossing and Road Pavement**

- C13. Prior to the issue of any Construction Certificate, security deposit or bank guarantee must be provided to Council to the sum of \$5,000.00 to be held by Council for the payment of cost for any/all of the following:

- a) making good any damage caused to any property of the Council as a consequence of the doing of anything to which this consent relates,
- b) completing any public work (such as road work, kerbing and guttering, footway construction, stormwater drainage and [environmental controls](#)) required in connection with this consent
- c) remedying any defects in any such public work that arise within 6 months after the work is completed.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate or completion of public work required to be completed (whichever is the latest) but only upon inspection and release by Council's Engineers.

Council shall have full authority to make use of the bond for such restoration works as deemed necessary by Council in circumstances including the following: -

- where the damage constitutes a hazard in which case Council may make use of the security immediately;
- the applicant has not repaired or commenced repairing damage within 48 hours of the issue by Council in writing of instructions to undertake such repairs or works;
- works in the public road associated with the development are to an unacceptable quality; and
- the Certifying Authority must ensure that security is provided to North Sydney Council prior to issue of any Construction Certificate.

(Reason: To ensure appropriate security for works on public land and an appropriate quality for new public infrastructure)

### **Tree Bond for Public Trees**

- C14. Prior to the issue of any construction certificate, security in the sum of \$38,000.00 must be provided to Council for the protection of trees in public places, including the making good of any damage caused to such trees. The security is to be provided in accordance with the Schedule below.

The security required by this condition and in the schedule contained later in these conditions must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

The security will be refundable following the expiration of 6 months from the issue of any final Occupation Certificate but only upon inspection and release by Council's Landscape Development Officer.

If any tree is removed or damaged Council may deduct from this security the reasonable cost of replacement with a tree of the same species and to a similar stage of growth it would have attained at the completion of the work.

In the case of any tree, which cannot be replaced with a similar specimen, the security for that tree will be forfeited to Council and used to provide replacement street plantings.

### SCHEDULE

<b>Tree Species</b>	<b>Location</b>	<b>Bond</b>
<i>Tristaniopsis laurina</i> (10x12m)	Council verge in front of 2a Winnie Street	\$5,000
Tree 3 1 x <i>Tristaniopsis laurina</i> (4.5mx3m)	Council verge in front of 4 Winnie Street	\$2,000
<i>Tristaniopsis laurina</i> (10x10m)	Council verge in front of 6 Winnie Street	\$5,000
2 x <i>Tristaniopsis laurina</i> (8x7m)	Either side of the existing driveway of the Gerard Street frontage of the SCECGS Redlands site	\$10,000
4 x <i>Lagerstroemia indica</i> (6x5m)	Council verge in front of the Gerard Street frontage of the SCECGS Redlands site	\$10,000

<i>Corymbia sp</i> (16 x 12m)	Council verge in front of 3 Monford Place	\$5,000
<i>Corymbia sp</i> (4x2m)	Council verge in front of 5 Monford Place	\$1,000

(Reason: Protection of existing environment public infrastructure, community assets and significant trees)

**Protection of Trees**

C15. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

<b>Tree</b>	<b>Location</b>	<b>Height</b>
<i>Tristaniopsis laurina</i>	Council verge in front of 2a Winnie Street	10x12m
Tree 3 <i>Tristaniopsis laurina</i>	Council verge in front of 4 Winnie Street	4.5mx3m
<i>Tristaniopsis laurina</i>	Council verge in front of 6 Winnie Street	10x10m
2 x <i>Tristaniopsis laurina</i>	Either side of the existing driveway of the Gerard Street frontage of the SCECGS Redlands site	8x7m
4 x <i>Lagerstroemia indica</i>	Council verge in front of the Gerard Street frontage of the SCECGS Redlands site	6x5m
<i>Corymbia sp</i>	Council verge in front of 3 Monford Place	16 x 12m
<i>Corymbia sp</i>	Council verge in front of 5 Monford Place	4x2m
Tree 1 <i>Cedrus deodara</i>	Within the rear setback of 2 Winnie Street	15x14m
5 x <i>Pyrus</i> ‘Capital’	Within the front setback of the Gerard Street frontage of the SCECGS Redlands site	5x4m

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

Any tree(s) shown as being retained on the approved plans (regardless of whether they are listed in the above schedule or not) must be protected and retained in accordance with this condition.

(Reason: Protection of existing environmental and community assets)

**Removal of Trees**

C16. Tree removal shall be in accordance with that specified within the report from Redgum Horticultural as revised on 10 March 2020 (Report Ref. 5609.1).

Removal of any other tree on the site is not approved, excluding species exempt under Council's Tree Preservation Order.

(Reason: Protection of existing environmental and community assets)

### **Pruning of Trees**

C17. All pruning works shall to the following tree shall be undertaken under the guidance of an appropriately qualified arborist/tree surgeon in accordance with Australian Standard AS 4373-2007 - Pruning of Amenity Trees:

<b>Trees that require pruning</b>	<b>Location</b>	<b>Height</b>
Tree 1 <i>Cedrus deodara</i>	Within the rear setback of 2 Winnie Street	15x14m

The pruning of selected branches of the above tree shall be as depicted in Section 14 of the arborist report prepared by Redgum Horticultural dated 10 March 2020. No other pruning to this tree shall be permitted.

(Reason: To ensure the protection and longevity of existing significant trees)

### **Asbestos Material Survey**

C18. A report must be prepared by a suitably qualified person in relation to the existing building fabric to be demolished and/or disturbed identifying the presence or otherwise of asbestos contamination and, if asbestos contamination is present, making recommendations as to the work required to safely address the contamination.

Any demolition works or other works identified in the report as having to be carried out must be carried out in accordance with the recommendations of the report and the following:

- a) the removal of asbestos must be undertaken by a WorkCover licensed contractor;
- b) all removal must be in strict accordance with the requirements of the WorkCover Authority in relation to the removal, handling and disposal of material containing asbestos and any Work Safe Australia requirements.
- c) during the removal of any asbestos a sign stating "DANGER ASBESTOS REMOVAL IN PROGRESS" must be erected in a visible position at the boundary of the site; and
- d) Waste disposal receipts must be provided to the Certifying Authority as proof of correct disposal of asbestos laden waste.

The report must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the report, and other plans, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily)

### Screen Planting

- C19. To maintain acceptable levels of privacy, screen planting must be installed and maintained adjacent to the southern boundary of the site in the location shown clouded red on the stamped approved plans. The required screen planting must consist of suitable screening species capable of attaining a mature height of 2.5 – 3.0 metres above finished ground levels.

Details of the screen planting required by this condition must be provided to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the details submitted fully satisfy the requirements of this condition.

(Reason: To preserve the privacy of the adjoining property)

### Security Deposit/ Guarantee Schedule

- C20. All fees and security deposits/ guarantees in accordance with the schedule below must be provided to Council prior to the issue of any Construction Certificate:

<b>Security deposit/ guarantee</b>	<b>Amount (\$)</b>
Footpath/Infrastructure Damage Bond	\$5,000.00
Bond for trees within public land	\$38,000.00
<b>TOTAL BONDS</b>	<b>\$43,000.00</b>

The security required by the above schedule must be provided by way of a deposit with the Council; or other such guarantee that is satisfactory to Council (such as a bank guarantee). Any guarantee provided as security must name North Sydney Council as the nominated beneficiary and must not be subject to an expiry date.

(Reason: Compliance with the development consent)

### Pruning of Trees

- C21. Non-invasive/non- destructive root mapping is to be undertaken within the tree protection zone (TPZ) (identified as per AS4970-2009) of the following tree to determine the size and depth of the tree roots prior to the design of the required footings for deck, paving, stormwater, or any related construction. Sensitive construction techniques including hand excavation, and the flexible siting of piers, pits, or pipework, is to be observed within the TPZ of this tree.

<b>Tree</b>	<b>Location</b>	<b>Height</b>
Tree 1 <i>Cedrus deodara</i>	Within the rear setback of 2 Winnie Street	15x14m

Root mapping is to be undertaken under the direct supervision of an AQF level 5 arborist. The said consulting/ project arborist is to prepare a written report, with images, addressing the following:

- a. describing the results of the root mapping;
- b. providing an assessment of potential tree impacts of the excavation; and
- c. making recommendations of protection measures to be implemented for the duration of excavation and construction activity to ensure the ongoing health and viability of the tree.

The report is to be provided to the Certifying Authority for approval (with a copy provided to Council) prior to the issue of any Construction Certificate. Plans and Specifications submitted to the Certifier for approval must comply with the recommendations of the arborist report referred to in this condition, and the development must be carried out in accordance with the said report.

(Reason: To ensure the protection of significant trees)

**D. Prior to the Commencement of any Works (and continuing where indicated)**

**Project Arborist to be Engaged**

D1. The project arboriculturist shall inspect tree protection measures and certify in writing to the Principal Certifying Authority the measures comply with the approved Tree Protection Plan and as directed by the project arboriculturist before work commences.

The project arboriculturist shall provide guidance and oversight of tree protection and management to ensure that the stability and ongoing viability of trees being retained is not compromised.

The project arboriculturist must contact the tree pruning contractor and Council's Tree Management Officer (giving at least 2 working days' notice) to arrange a joint site meeting, prior to commencing any pruning, to determine the exact location and extent of pruning that is permissible, with the tree pruning contractor to comply with any instructions issued by Council, acting reasonably.

Any pruning must be undertaken by a practicing arborist with a minimum Australian Qualification Framework Level 3 in arboriculture, in accordance with the principles of the Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and the NSW Work Cover Code of Practice for the Amenity Tree Industry (1998), as well as any instructions issued on site by Council, acting reasonably.

The practicing arborist must keep a log of dates and times of when they attended the site, the type of works that were performed, and must form part of the certification required prior to Occupation.

(Reason: Tree protection measures)

**Protection of Public Trees**

D2. The following tree(s) are required to be protected and retained as part of the development consent in accordance with AS 4970-2009 – Protection of trees on development sites:

<b>Tree Species</b>	<b>Location</b>	<b>Tree Protection</b>
<i>Tristaniopsis laurina</i> (10x12m)	Council verge in front of 2a Winnie Street	1.8m high steel mesh tree protection fencing, branch protection
Tree 3 1 x <i>Tristaniopsis laurina</i> (4.5mx3m)	Council verge in front of 4 Winnie Street	1.8m high steel mesh tree protection fencing

<i>Tristaniopsis laurina</i> (10x10m)	Council verge in front of 6 Winnie Street	1.8m high steel mesh tree protection fencing, branch protection
2 x <i>Tristaniopsis laurina</i> (8x7m)	Either side of the existing driveway of the Gerard Street frontage of the SCECGS Redlands site	1.8m high steel mesh tree protection fencing, branch protection
4 x <i>Lagerstroemia indica</i> (6x5m)	Council verge in front of the Gerard Street frontage of the SCECGS Redlands site	1.8m high steel mesh tree protection fencing, branch protection
<i>Corymbia sp</i> (16 x 12m)	Council verge in front of 3 Monford Place	Trunk protection
<i>Corymbia sp</i> (4x2m)	Council verge in front of 5 Monford Place	1.8m high steel mesh tree protection fencing

Plans and specifications complying with this condition must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate. The Certifying Authority must ensure that the building plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: Protection of existing environmental and community assets)

### **Property Boundary Fencing**

D3. New property boundary fencing alongside/rear boundaries shall be lapped and capped with no gaps. The new fencing shall be provided in consultation with adjoining neighbours with the civil legal rights of those neighbours being observed at all times.

(Reason: To ensure appropriate retention and replacement of existing boundary treatment around the perimeter of the site)

### **Protection of Trees**

D4. All trees that are specifically nominated to be retained by notation on plans or by condition as a requirement of this consent must be maintained and protected during demolition, excavation and construction on the site in accordance with AS4970-2009 (Protection of trees on development sites). A report containing recommendations, and methods of tree protection prepared by an appropriately qualified person must be provided to the Certifying Authority for approval by an appropriately qualified person prior to commencement of any works on the site. Any recommendations must be undertaken for the duration of works on the site.

(Reason: To ensure compliance with the requirement to retain significant planting on the site)

### **Temporary Fences and Tree Protection**

D5. All protected trees on-site that are specifically nominated **as per Condition C15 of this consent** are to be retained by notation on plans or by condition as a requirement of this consent must be tagged with luminous tape or the like for purposes of identification prior to demolition, excavation or construction works and must remain so for the duration of works on the site. No materials or builder's waste are to be stored in the vicinity of the nominated tree/trees at any time.

Appropriate fencing or barricades in accordance with AS4970-2009 (Protection of trees on development sites), not less than the distance shown in the schedule hereunder, must be installed to the satisfaction of the Certifying Authority prior to demolition or commencement of any works and must be maintained for the duration of the works: -

(Reason: To protect the trees to be retained on the site during construction works)

### **Public Liability Insurance – Works on Public Land**

D6. Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of public land and the undertaking of approved works within Council's road reserve or public land, as approved by this consent. The Policy is to note, and provide protection/full indemnification for North Sydney Council, as an interested party. A copy of the Policy must be submitted to Council prior to commencement of any works. The Policy must be valid for the entire period that the works are being undertaken.

(Note: Applications for hoarding permits, vehicular crossings etc will require evidence of insurance upon lodgement of the application.)

(Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land)

### **Sydney Water Approvals**

D7. Prior to the commencement of any works, the approved plans must be submitted to Sydney Water to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The Certifying Authority must ensure that Sydney Water has appropriately stamped the plans before the commencement of building works.

Notes:

- **Sydney Water Building Plan Approvals** can be obtained from the Sydney Water Tap in™ online service. Building plans must be submitted to the Tap in™ to determine whether the development will affect any Sydney Water sewer or water main, stormwater drains and/or easement, and if further requirements need to be met. For further information visit <http://www.sydneywater.com.au/tapin/index.htm> or call 13 000 TAP IN (1300 082 746) for further information.

(Reason: To ensure compliance with Sydney Water requirements)

### **Commencement of Works Notice**

D8. Building work, demolition or excavation in accordance with this development consent must not be commenced until the developer has given at least 2 days notice to North Sydney Council of the person's intention to commence building work, demolition or excavation in accordance with this development consent.

(Reason: To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)



***E. During Demolition and Building Work***

**Service Adjustments**

- E1. Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the person acting on the consent and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council.

It is the Applicants full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services at the appropriate stage of the development (including water, phone, gas and the like).

Council accepts no responsibility whatsoever for any matter arising from its approval of this application involving any influence upon utility services provided by another authority.

(Reason: To ensure the service requirements are met).

**Cigarette Butt Receptacle**

- E2. A cigarette butt receptacle is to be provided on the site for the duration of excavation/demolition/construction process, for convenient use of site workers.

(Reason: To ensure adequate provision is made for builders' waste)

**Parking Restrictions**

- E3. Existing public parking provisions in the vicinity of the site must be maintained at all times during works. The placement of any barriers, traffic cones, obstructions or other device in the road shoulder or kerbside lane is prohibited without the prior written consent of Council. Changes to existing public parking facilities/restrictions must be approved by the North Sydney Local Traffic Committee. The Developer will be held responsible for any breaches of this condition, and will incur any fines associated with enforcement by Council regulatory officers.

(Reason: To ensure that existing kerbside parking provisions are not compromised during works)

**Road Reserve Safety**

- E4. All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works, with no obstructions caused to the said footways and roadways. Construction materials and plant must not be stored in the road reserve without approval of Council. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site.

Where public infrastructure is damaged, repair works must be carried out in when and as directed by Council officers (at full Developer cost). Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". **If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.**

(Reason: Public Safety)

### **Temporary Disposal of Stormwater Runoff**

E5. During construction, stormwater runoff must be disposed in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to reasonably manage and control runoff as far as the approved point of stormwater discharge. Such ongoing measures must be to the satisfaction of the Certifying Authority.

(Reason: Stormwater control during construction)

### **Removal of Extra Fabric**

E6. Should any portion of the existing building, trees, or curtilage of the site which is indicated on the approved plans to be retained be damaged for whatever reason, all the works in the area of the damaged portion are to cease and written notification of the damage is to be given to Council forthwith. No work is to resume until the written approval of Council to do so is obtained. Failure to comply with the provisions of this condition may result in the Council taking further action including legal proceedings if necessary.

(Reason: To ensure compliance with the terms of this development consent)

### **Dust Emission and Air Quality**

E7. The following must be complied with at all times:

- (a) Materials must not be burnt on the site.
- (b) Vehicles entering and leaving the site with soil or fill material must be covered.
- (c) Dust suppression measures must be carried out to minimise wind-borne emissions in accordance with the NSW Department of Housing's 1998 guidelines - Managing Urban Stormwater: Soils and Construction.
- (d) Odour suppression measures must also be carried out where appropriate so as to prevent nuisance occurring at adjoining properties.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

### **Noise and Vibration**

- E8. The works must be undertaken in accordance with the “Interim Construction Noise Guideline” published by the NSW Environment Protection Authority, to ensure excessive levels of noise and vibration do not occur so as to minimise adverse effects experienced on any adjoining land.

(Reason: To ensure residential amenity is maintained in the immediate vicinity)

### **Developer's Cost of Work on Council Property**

- E9. The developer must bear the cost of all works associated with the development that occurs on Council’s property, including the restoration of damaged areas.

(Reason: To ensure the proper management of public land and funds)

### **No Removal of Trees on Public Property**

- E10. No trees on public property adjacent to the site (footpaths, roads, reserves, etc.) shall be removed or damaged during construction including for the erection of any fences, hoardings or other temporary works, unless specifically approved by the conditions of this consent.

(Reason: Protection of existing environmental infrastructure and community assets)

### **Protection of Trees**

- E11. All trees required to be retained, as part of this consent must be protected from any damage during construction works in accordance with AS4970-2009. All recommendations contained within the tree report prepared by must be implemented for the duration of the works.

Strict adherence to the tree protection measures prescribed within the approved arborist report prepared Redgum Horticultural dated 10 March 2020 shall be heeded at all stages of the demolition and construction works.

In the event that any tree required to be retained is damaged during works on the site, notice of the damage must be given to Council forthwith.

#### Notes:

1. If the nominated tree is damaged to a significant degree or removed from the site without prior written approval being obtained from Council, the issuing of fines or legal proceedings may be commenced for failure to comply with the conditions of this consent.
2. An application to modify this consent pursuant to Section 4.66 of the Environmental Planning and Assessment Act 1979 will be required to address the non-compliance with any of the conditions of consent relating to the retention of nominated trees, and Council may require tree replenishment.

(Reason: Protection of existing environmental infrastructure and community assets)

## **Special Permits**

- E12. Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development must occur entirely on the property.

The developer, owner or builder may apply for specific permits available from Council's Customer Service Centre for the undermentioned activities on Council's property. In the event that a permit is granted by Council for the carrying out of works, processes, storage of materials, loading and unloading associated with the development on Council's property, the development must be carried out in accordance with the requirements of the permit. A minimum of forty-eight (48) hours notice is required for any permit: -

1) **On-street mobile plant**

Eg. cranes, concrete pumps, cherry-pickers, etc. - restrictions apply to the hours of operation, the area of operation, etc. Separate permits are required for each occasion and each piece of equipment. It is the developer's, owner's and builder's responsibilities to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

(Reason: Proper management of public land)

2) **Hoardings**

Permits are required to erect Class A and Class B hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

(Reason: Proper management of public land)

3) **Storage of building materials and building waste containers (skips) on Council's property**

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given. Storage of building materials and waste containers on open space reserves and parks is prohibited.

(Reason: Proper management of public land)

4) **Kerbside restrictions, construction zones**

Attention is drawn to the existing kerbside restrictions adjacent to the development. Should alteration of existing kerbside restrictions be required, or the provision of a construction zone, the appropriate application must be made and the fee paid to Council. Alternatives to such restrictions may require referral to Council's Traffic Committee and may take considerable time to be resolved. An earlier application is suggested to avoid delays in construction programs.

(Reason: Proper management of public land)

### **Construction Hours**

E13. Building construction and works must be restricted to within the hours of 7.00 am to 5.00 pm Monday to Friday and on Saturday to within the hours of 8.00 am to 1.00 pm inclusive, with no work on Sundays and Public Holidays.

Demolition and excavation works must be restricted to within the hours of 8.00 am to 5.00 pm Monday to Friday only. For the purposes of this condition:

- a) “Building construction” means any physical activity on the site involved in the erection of a structure, cladding, external finish, formwork, fixture, fitting of service installation and the unloading of plant, machinery, materials or the like.
- b) “Demolition works” means any physical activity to tear down or break up a structure (or part thereof) or surface, or the like, and includes the loading of demolition waste and the unloading of plant or machinery.
- c) “Excavation work” means the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders, or the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site and includes the unloading of plant or machinery associated with excavation work.

All builders, excavators must display, on-site, their twenty-four (24) hour contact telephone number, which is to be clearly visible and legible from any public place adjoining the site.

(Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community)

### **Installation and Maintenance of Sediment Control**

E14. Erosion and sediment controls must be installed and maintained at all times in accordance with the Sediment and erosion control plan submitted and approved with the Construction Certificate.

Erosion and sediment measures must be maintained in accordance with the publication Managing Urban Stormwater: Soils & Construction (4th edition, Landcom, 2004), commonly referred to as the “Blue Book” and can only be removed when development activities have been completed and the site fully stabilised.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

### **Sediment and Erosion Control Signage**

E15. A durable sign must be erected during building works in a prominent location on site, warning of penalties should appropriate erosion and sedimentation control devices not be maintained. A sign of the type referred to in this condition is available from Council.

(Reason: To protect the environment from the effects of sedimentation and erosion from development sites)

### **Site Amenities and Facilities**

- E16. Where work involved in the erection and demolition of a building is being carried out, amenities which satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements, must be provided and maintained at all times. The type of work place determines the type of amenities required.

Further information and details can be obtained from the Internet at [www.workcover.nsw.gov.au](http://www.workcover.nsw.gov.au)

(Reason: To ensure the health and safety of the community and workers on the site)

### **Health and Safety**

- E17. All work undertaken must satisfy applicable occupational health and safety and construction safety regulations, including any WorkCover Authority requirements to prepare a health and safety plan. Site fencing must be installed sufficient to exclude the public from the site. Safety signs must be erected that warn the public to keep out of the site, and provide a contact telephone number for enquiries.

Further information and details regarding occupational health and safety requirements for construction sites can be obtained from the internet at [www.workcover.nsw.gov.au](http://www.workcover.nsw.gov.au)

(Reason: To ensure the health and safety of the community and workers on the site)

### **Prohibition on Use of Pavements**

- E18. Building materials must not be placed on Council's footpaths, roadways, parks or grass verges, (unless a permit is obtained from Council beforehand). A suitable sign to this effect must be erected adjacent to the street alignment.

(Reason: To ensure public safety and amenity on public land)

### **Plant & Equipment Kept Within Site**

- E19. All plant and equipment used in the undertaking of the development/ works, including concrete pumps, wagons, lifts, mobile cranes, hoardings etc, must be situated within the boundaries of the site (unless a permit is obtained from Council beforehand) and so placed that all concrete slurry, water, debris and the like must be discharged onto the building site, and is to be contained within the site boundaries.

Details of Council requirements for permits on public land for standing plant, hoardings, storage of materials and construction zones and the like are available on Council's website at [www.northsydney.nsw.gov.au](http://www.northsydney.nsw.gov.au).

(Reason: To ensure public safety and amenity on public land)

### **Waste Disposal**

E20. All records demonstrating the lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as North Sydney Council and the Environmental Protection Authority.

(Reason: To ensure the lawful disposal of construction and demolition waste)

### **Asbestos Removal**

E21. All demolition works involving the removal and disposal of asbestos cement must only be undertaken by contractors who hold a current WorkCover Asbestos or “Demolition Licence” and a current WorkCover “Class 2 (Restricted) Asbestos Licence and removal must be carried out in accordance with National Occupational Health and Safety Commission.

(Reason: To ensure works are carried out in accordance with relevant WorkCover requirements)

### ***F. Prescribed Conditions imposed under EP&A Act and Regulations and other relevant Legislation***

#### **National Construction Code**

F1. All building work must be carried out in accordance with the provisions of the National Construction Code.

(Reason: Prescribed - Statutory)

#### **Home Building Act**

F2. 1) Building work that involves residential building work (within the meaning and exemptions provided in the Home Building Act 1989) for which the *Home Building Act* 1989 requires there to be a contract of insurance under Part 6 of that Act must not be carried out unless the Principal Certifying Authority for the development to which the work relates has given North Sydney Council written notice of the contract of insurance being issued and of the following:

- a) in the case of work for which a principal contractor is required to be appointed:
  - i) the name and licence number of the principal contractor, and
  - ii) the name of the insurer by which the work is insured under Part 6 of that Act, or
- (b) in the case of work to be done by an owner-builder:
  - (i) the name of the owner-builder, and
  - (ii) if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

- 2) If arrangements for doing residential building work are changed while the work is in progress such that the information submitted to Council in accordance with this conditions is out of date, work must cease and no further work may be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council), has given the Council written notice of the updated information.

Note: A certificate purporting to be issued by an approved insurer under Part 6 of the Home Building Act 1989 that states that a person is the holder of an insurance policy issued for the purposes of that Part is, for the purposes of this clause, sufficient evidence that the person has complied with the requirements of that Part.

(Reason: Prescribed - Statutory)

### **Appointment of a Principal Certifying Authority (PCA)**

- F3. Building work, demolition or excavation in accordance with the development consent must not be commenced until the developer has appointed a Principal Certifying Authority for the building work in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

### **Construction Certificate**

- F4. Building work, demolition or excavation in accordance with the development consent must not be commenced until a Construction Certificate for the relevant part of the building work has been issued in accordance with the provisions of the EP&A Act and its Regulations.

(Reason: Statutory; To ensure appropriate safeguarding measures are in place prior to the commencement of any building work, demolition or excavation)

### **Occupation Certificate**

- F5. A person must not commence occupation or use of the whole or any part of a new building (*new building* includes an altered portion of, or an extension to, an existing building) unless an Occupation Certificate has been issued in relation to the building or part. Only the Principal Certifying Authority appointed for the building work can issue an Occupation Certificate.

(Reason: Statutory)

### **Excavation/Demolition**

- F6. 1) All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
- 2) All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.



- 3) Demolition work must be undertaken in accordance with the provisions of AS2601-Demolition of Structures.

(Reason: To ensure that work is undertaken in a professional and responsible manner and protect adjoining property and persons from potential damage)

### **Protection of Public Places**

- F7.
- 1) A hoarding and site fencing must be erected between the work site and adjoining public place.
  - 2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
  - 3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
  - 4) Any such hoarding, fence or awning is to be removed when the work has been completed.
  - 5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained. Any application needs to be accompanied by plans indicating the type of hoarding and its layout. Fees are assessed and will form part of any approval given. These fees must be paid prior to the approval being given. Approval for hoardings will generally only be given in association with approved building works, maintenance or to ensure protection of the public. An application form for a Hoarding Permit can be downloaded from Council's website.

(Reason: To ensure public safety and the proper management of public land)

### **Site Sign**

- F8.
- 1) A sign must be erected in a prominent position on the site
    - a) stating that unauthorised entry to the work site is prohibited;
    - b) showing the name of the principal contractor (or person in charge of the work site), and a telephone number at which that person may be contacted at any time for business purposes and outside working hours; and
    - c) showing the name, address and telephone number of the Principal Certifying Authority for the work.
  - 2) Any such sign must be maintained while to building work or demolition work is being carried out, but must be removed when the work has been completed.

(Reason: Prescribed - Statutory)

**G. Prior to the Issue of an Occupation Certificate**

**Noise Certification**

G1. Prior to issue of the any Occupation Certificate a certificate from an appropriately qualified acoustical consultant eligible for membership of the Association of Australian Acoustic Consultants is to be submitted to, and approved by, the Certifying Authority certifying that the noise and vibration from use of the development complies with the conditions of consent herein.

(Reason: To ensure acoustic amenity)

**Infrastructure Repair and Completion of Works**

G2. Prior to the issue of any Occupation Certificate any and all works relating to the development:

- a. in the road reserve must be fully completed; and
- b. to repair and make good any damaged public infrastructure caused as a result of any works relating to the development (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub-contractors, concrete vehicles) must be fully repaired;

to the satisfaction of Council Engineers at no cost to Council.

(Reason: Maintain quality of Public assets)

**Damage to Adjoining Properties**

G3. All precautions must be taken to prevent any damage likely to be sustained to adjoining properties. Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.

(Reason: To ensure adjoining owner's property rights are protected)

**Utility Services**

G4. All utility services shall be adjusted, to the correct levels and/or location/s required by this consent, prior to issue of an occupation certificate. This shall be at no cost to Council.

(Reason: To ensure compliance with the terms of this consent)

**Covenant & Restriction (Stormwater Control Systems)**

G5. An Instrument pursuant to Sections 88B and 88E of the *Conveyancing Act* 1919 and one copy must be submitted to Council in registrable form, providing for:

- a. a restriction as to user and positive covenant as to user as appropriate in favour of North Sydney Council burdening 2 Winnie Street requiring the ongoing retention, maintenance and operation of the stormwater facility (on-site detention, pump-out, charged lines);

- b. North Sydney Council being nominated in the Instrument as the only party authorised to release, vary or modify the Instrument;
- c. the wording on the Instrument making reference to the Council file/s which hold:
  - (a) the Construction plans; and
  - (b) the “Work-as-Executed” (as built) plans;

Upon Council being satisfied as to the terms of the Instrument, North Sydney Council’s official seal will be affixed to these documents, prior to submission to the Land & Property Information Office for registration

The Instrument creating the restriction and/or covenant under ss 88B and 88E required by this condition of consent must be registered on the Title of the development site prior to the issue of an Occupation Certificate or commencement of use of the site, whichever is the earlier. Typical wording for the Instrument can be sourced from Council’s “Specification for the Management of Stormwater”.

Evidence of the registration of the instrument referred to in this condition is to be provided to Council prior to the issue of an Occupation Certificate.

All costs associated with the preparation, approval and registration of the Instrument required by this condition of consent must be borne by the person acting on this consent including the reasonable costs of Council in obtaining advice, negotiating the terms or otherwise facilitating the execution and registration of the required Instrument.

(Reason: Compliance and adequate maintenance of drainage system)

### **Asbestos Clearance Certificate**

- G6. For building works where asbestos based products have been removed or altered, an asbestos clearance certificate signed by an appropriately qualified person (being an Occupational Hygienist or Environmental Consultant) must be submitted to and approved by the Certifying Authority (and a copy forwarded to Council if it is not the Certifying Authority) for the building work prior to the issue of any Occupation Certificate, the asbestos clearance certificate must certify the following: -
- a) the building/ land is free of asbestos; or
  - b) the building/ land has asbestos that is presently deemed safe.

The certificate must also be accompanied by tipping receipts, which detail that all asbestos waste has been disposed of at an approved asbestos waste disposal depot. If asbestos is retained on site the certificate must identify the type, location, use, condition and amount of such material.

Note: Further details of licensed asbestos waste disposal facilities can be obtained from [www.epa.nsw.gov.au](http://www.epa.nsw.gov.au)

(Reason: To ensure that building works involving asbestos based products are safe for occupation and will pose no health risks to occupants)

**Certification of Tree Condition**

- G7. Prior to the issue of an Occupation Certificate, a report prepared by an appropriately qualified person (being an arborist or the like) must be submitted to the Certifying Authority, describing the health of the trees specifically nominated below: -

<b>Tree</b>	<b>Location</b>	<b>Height</b>
<i>Tristaniopsis laurina</i>	Council verge in front of 2a Winnie Street	10x12m
Tree 3 <i>Tristaniopsis laurina</i>	Council verge in front of 4 Winnie Street	4.5mx3m
<i>Tristaniopsis laurina</i>	Council verge in front of 6 Winnie Street	10x10m
2 x <i>Tristaniopsis laurina</i>	Either side of the existing driveway of the Gerard Street frontage of the SCECGS Redlands site	8x7m
4 x <i>Lagerstroemia indica</i>	Council verge in front of the Gerard Street frontage of the SCECGS Redlands site	6x5m
<i>Corymbia sp</i>	Council verge in front of 3 Monford Place	16 x 12m
<i>Corymbia sp</i>	Council verge in front of 5 Monford Place	4x2m
Tree 1 <i>Cedrus deodara</i>	Within the rear setback of 2 Winnie Street	15x14m
5 x <i>Pyrus</i> 'Capital'	Within the front setback of the Gerard Street frontage of the SCECGS Redlands site	5x4m

The report must detail the condition and health of the nominated trees upon completion of the works and shall certify that the trees have not been significantly damaged during the works on the site and have reasonable prospects for survival.

(Reason: To ensure compliance with the terms of this consent)

**Landscaping**

- G8. The landscaping proposals including all tree planting shown on the approved landscape plan listed in Condition A1 of this consent, as extended by Condition C4 of this consent must be completed in full prior to the issue of any Occupation Certificate.

(Reason: To ensure compliance).

**Compliance with Certain conditions**

- G9. Prior to the issue of any Occupation Certificate Conditions **C3**, **C4** and **G7** must be certified as having been implemented on site and complied with.

(Reason: To ensure the development is completed in accordance with the requirements of this consent)

**I. On-Going / Operational Conditions**

**Noise and Vibration**

- I1. The on-going use of the premises approved under this consent must comply with all conditions pertaining to noise and vibration specified in this consent.

(Reason: To ensure compliance with the specified levels of noise and vibration and to maintain the amenity of surrounding land uses)

### **Classroom use**

12. a) The classrooms are to be used for general learning activities and not for noise generating activities such music teaching, or activities that rely on noise generating plant or equipment for teaching and learning.
- b) External areas around the classrooms are for circulation only and are not to be used as play areas.
- c) There shall be no provision for Public Address System Announcements within the site, unless expressly permitted in writing by Council.

(Reason: To maintain the amenity of surrounding land uses).

### **Hours of Operation**

13. The hours of operation of the classrooms shall be restricted to between 8am and 5pm Monday until Friday only. The classrooms are not to be used on weekends or during school holidays.

(Reason: To ensure that amenity of the surrounding locality is maintained)

### **Ongoing Street Tree Care**

14. The 3 x *Tristaniopsis laurina* located in the road reserve in front of 2A - 6 Winnie Street shall be watered for a period of six (6) months after the final construction certificate is issued. The watering shall be approximately 20 litres per week (min) delivered gently by hose or watering can so that the surrounding soil can absorb the water. Seasol solution is recommended once a month over this period.

Plans and specifications showing the said tree protection measures must be submitted to the Certifying Authority for approval prior to the issue of any Construction Certificate.

The Certifying Authority must ensure the construction plans and specifications submitted, referenced on and accompanying the issued Construction Certificate, fully satisfy the requirements of this condition.

(Reason: To ensure that appropriate tree protection measures are shown on construction drawings)

### **Maintenance of Approved Landscaping**

15. The owners of the property are to maintain the landscaping approved by this consent generally in accordance with the landscaping plans listed in Condition A1 of this consent.

Any replacement plants required shall be advanced in growth and be selected to maintain the anticipated mature height, canopy density and nature of those plant species as originally approved.

(Reason: To ensure the amenity of the locality is maintained)